Job Agent Explained

Haatim Ali
October 29, 2026

CONTENTS

Job Agent Explained

Part 1: The big picture

- The one-sentence version
- The 30-second explanation
- System map
- The components at a glance
- Where everything physically lives

Part 2: The life of one job

Part 3: The server and how things run on it

- The VPS
- Getting in: SSH
- The Python virtual environment
- cron: the scheduler
- systemd: keeping the bot alive
- Logs
- Watchdog: knowing when something stops
- Backups
- Configuration and secrets

Part 4: Collecting and filtering jobs (scraper.py, career_sites.py)

- Source 1: LinkedIn through JobSpy
- Source 2: company job boards (career_sites.py)
- The adapter pattern
- Workday, SmartRecruiters and the SimplifyJobs list (added 2026-10-01)
- Details the adapters handle
- The filter funnel (process_jobs)
- 1. Seen check
- 2. quick_filter: free string checks
- 3. Full page fetch (LinkedIn only)
- 4. Experience filter (a regular expression)
- 5. Duplicates and reposts
- 6. Freshness OR filter (LinkedIn only)
- Claude scoring (claude_relevance_check)

- The prompt
- Reading the answer
- Error handling: errors are not rejections
- The alert
- Tailored files with every alert

Part 5: The Discord bot (bot.py)

- How a Discord bot works
- Events the bot handles
- Reactions
- The #requests channel: a small state machine
- Commands

Part 6: Documents and applications

- Resume tailoring (tailor.py + resume_tailor.py)
- A short LaTeX primer
- The pipeline, one call at a time
- How resume edits are kept truthful
- Sending the result
- Application packets (apply_prep.py)
- The queue
- Finding LinkedIn jobs on the company's own board (find_on_ats)
- Reading the real form
- Drafting the answers
- Which contact details go where
- Validating the answers in code
- The packet
- Submitting (on your Mac)
- The watcher: filling without being asked
- Filling fast: the fill plan (form_fill.py)
- Posting to #applications (post_discord)

Part 7: Data

- SQLite primer
- The tables
- The feedback loop (how it "learns")
- Why data lives in two places

Part 8: Outside services
- Google Sheets (sheets_sync.py)
- Access
- Sheet layout (since 2026-10-29)
- Where a row goes (find_row)
- Resume
- Rejections from email
- Fail soft
- Gmail inbox check (email_scan.py)
- Discord
- Anthropic (Claude)

Part 9: Testing, deployment and operations
- Tests
- Where the code lives and how it's deployed
- Troubleshooting runbook

Part 10: Design decisions and limitations
- Design decisions worth explaining
- Known limitations

Glossary

Changelog

Job Agent Explained

A complete technical guide to the Job Agent: every component, every file, how data moves between them, and why each piece is built the way it is. Technical terms are explained the first time they appear, and every one of them is also in the **Glossary** at the end.

This is a living document. It is updated whenever the code, configuration or deployment changes (see the Changelog at the end).

How to read it. Part 1 is the big picture. Part 2 follows one job posting from the internet all the way to a submitted application. Parts 3 to 6 go component by component, in the order data flows through them. Part 7 covers data storage, Part 8 the outside services, Part 9 testing and operations. If you only have five minutes, read Part 1 and the 30-second explanation.

Numbers in this document were read from the live system on 2026-09-30 unless noted.

Part 1: The big picture


The one-sentence version

A scraper runs every 30 minutes on a rented Linux server, pulls new internship postings from LinkedIn and company job boards, filters them down with cheap rules and then with Claude, and posts the good ones to Discord. For company-job-board postings it also prepares a ready-to-submit **application packet** (tailored resume, cover letter, and an answer for every question on the application form). A Discord bot turns your emoji reactions into actions, and on your Mac, Claude fills application forms in Chrome while you click Submit.

The 30-second explanation

> ”It’s an event-driven pipeline. A cron-scheduled Python scraper pulls postings from LinkedIn and directly from company job boards through small per-source adapters, then runs them through a cost-ordered filter funnel: dedupe, regex, freshness. Only the survivors go to Claude Haiku for a structured JSON fit score. Matches are pushed to Discord by webhook. A separate always-on Discord bot turns emoji reactions into actions: logging applications to a database and my Google Sheet, tailoring my resume with Claude Sonnet and LaTeX under strict fact-checking, and capturing rejection reasons that get fed back into the scoring prompt, so the filter adapts without retraining. For company career-site jobs it also reads each application form’s real questions from the applicant tracking system, drafts validated answers, and hands me a ready packet; a Claude Code skill fills the form in my browser and I do the CAPTCHA and click Submit.”

System map



Job Agent architecture

The components at a glance

Component	What it is	How it runs	Lives in
`scraper.py`	Finds, filters and scores jobs, sends alerts, queues packets	**cron job** every 30 minutes: starts, does one pass, exits	VPS
`career_sites.py`	Adapters that pull postings from company job boards	Called by the scraper at the start of each run	VPS
`bot.py`	Discord bot: reactions, commands, #requests conversations	**systemd service**: always running, restarted if it crashes	VPS
`tailor.py`	Tailored resume + cover letter, compiled to PDF	A separate process started by the bot (👍) or by `apply_prep.py`	VPS
`resume_tailor.py`	The rules that keep resume edits truthful and the layout identical	Imported by `tailor.py`	VPS
`apply_prep.py`	Application queue, packet builder, #applications notices	Started by the scraper at the end of each run; also a command-line tool	VPS
`sheets_sync.py`	Writes applications into the Google Sheet tracker	Imported by the bot and `apply_prep.py`	VPS
`email_scan.py`	Reads htali@ucsc.edu (read-only) and updates the tracker from rejections, assessments and interviews	cron twice a day, `!inbox`	VPS
`jobs.db`	SQLite database file shared by everything above	A single file	VPS
`/submit-applications`	Claude Code skill that fills forms in Chrome	You run it on your Mac ("submit my queue")	Mac, `~/.claude/skills/`
Google Sheet	Your personal application tracker	Google's servers	Google Drive
Discord server	#job-alerts, #applications, #requests, #general	Discord's servers	Discord


Where everything physically lives

There are five places this system touches, and it helps to keep them straight:

1. **The VPS** (its address lives only in `~/.ssh/config` on your Mac, under the alias `jobagent-vps`, never in the public repo), rented from Hostinger. All the automation runs here. It is a virtual machine running **Debian 13** Linux with 2 CPU cores, 7.8 GB of memory and a 99 GB disk (10% used). The code lives in `/home/Haatim/job-agent/job-scout`.
2. **Your Mac.** The development copy of the code (`~/job-agent`, a git repository on branch `vps`), this document, and the Claude Code skills. Submitting applications happens here, in your own Chrome.
3. **Discord.** Where alerts arrive and where you react.
4. **Google Sheets.** Your tracker spreadsheet.
5. **Anthropic's API.** Every Claude call goes out over the internet to Anthropic's servers and comes back with a response.

Part 2: The life of one job

This is the whole system end to end, following a single posting. Every step is expanded later in the document.



From posting to submitted application

Step by step, for the Figma Software Engineer Intern (Summer 2027) posting:

1. **7:30 PM.** cron starts `scraper.py`.
2. `career_sites.py` downloads Figma's whole job list from Greenhouse's public API. The title contains "Intern" and "Software" and none of the excluded words; it was published within 72 hours; it passes.
3. The scraper checks `seen_jobs`: never seen. Cheap filters pass (not an excluded company, no "5+ years" text).
4. Claude Haiku reads the posting and your candidate profile and replies with a fit score of 9/10.
5. The scraper posts an embed to #job-alerts, marks the job seen, and adds it to `apply_queue`.
6. After all searches finish (about 12 minutes), the scraper launches `apply_prep.py --pending 3`.
7. `apply_prep.py` reads the application form's 23 questions from Greenhouse, runs the tailoring pipeline (5 Claude Sonnet calls plus `pdflatex`), drafts every answer (1 more Sonnet call), validates them, writes the packet folder, and posts "📦 Packet ready" in #applications.
8. Later, you say "submit my queue" in Claude Code. It copies the packet to your Mac, opens the form in your Chrome, fills every field and uploads the tailored resume.
9. You review, do the CAPTCHA if shown, click **Submit application**, and say "done."
10. Claude runs `apply_prep.py --submitted <url>` on the VPS over SSH: the job is marked submitted, logged in the `applications` table, announced in #applications with the resume attached (and a ping to you), and written to the Google Sheet with a link to that exact resume.

Part 3: The server and how things run on it

The VPS

A **VPS** (virtual private server) is a slice of a physical server in a data center, sold as if it were your own computer. It has its own operating system, disk and IP address, and it never sleeps. That is the whole reason the project uses one: a laptop closes; a VPS keeps running at 3 AM.

- **Operating system:** Debian 13 (“trixie”), a Linux distribution.
- **Python:** 3.13.5.
- **Managed from:** Hostinger’s control panel (**hPanel**) for billing, reboots and snapshots.
- **User account:** `Haatim`, which has `sudo` (permission to run commands as the administrator, `root`).

Getting in: SSH

SSH (Secure Shell) is an encrypted remote terminal. When Claude runs `ssh jobagent-vps '...'` from your Mac, the command executes on the VPS and the output comes back.

Authentication uses a **key pair** instead of a password: a private key (`~/.ssh/id_ed25519` on your Mac, never shared) and a matching public key installed on the server. The server sends a challenge that only the private key can sign. `ed25519` is the name of the modern elliptic-curve algorithm used.

scp (secure copy) uses the same connection to copy files, which is how code is deployed and packets are downloaded.

The Python virtual environment

The code runs with `/home/Haatim/job-agent/job-scout/venv/bin/python`, not the system Python. A **virtual environment** (venv) is a private folder of Python packages for one project, so upgrading a library for this project can never break another program on the server, and vice versa.

Key packages and the versions installed on the VPS:

Package	Version	Used for
`python-jobspy`	1.1.82	Scraping LinkedIn search results
`anthropic`	0.120.0	Official Claude API client
`discord.py`	2.7.1	The always-on bot
`discord-webhook`	1.4.1	Posting alerts through a webhook
`gspread`	6.2.1	Google Sheets API client
`requests`	2.34.2	Plain HTTP calls (job board APIs, Discord REST)
`beautifulsoup4`	4.15.0	Parsing HTML
`playwright`	1.62.0	Headless browser fallback for pages that need JavaScript
`pypdf`	6.14.2	Counting PDF pages and lines; reading PDFs sent to #requests
`PyYAML`	6.0.3	Reading `.yaml` config files
`python-dotenv`	1.2.2	Loading secrets from `.env`

cron: the scheduler

cron is the classic Linux job scheduler. Its configuration (the **crontab**) for user `Haatim`:

```
*/30 * * * * flock -n /tmp/jobscraper.lock /home/Haatim/job-agent/job-scout/venv/bin/python /home/Haatim/job-agent/job-scout/scraper.py
15 3 * * * /home/Haatim/job-agent/job-scout/venv/bin/python /home/Haatim/job-agent/job-scout/backup_db.py >> /var/log/jobscout_backup.log 2>&1
```

The five fields are minute, hour, day of month, month, day of week. `*/30` in the minute field means "every minute divisible by 30," so the scraper starts at :00 and :30 every hour. `flock -n` takes a lock on a file before starting; if the previous run still holds it, `-n` ("non-blocking") makes this run skip instead of overlapping. The second line backs up the database every night at 3:15 (see "Backups"). Each run is a brand-new process: it starts, does one full pass, and exits. A run currently takes about 12 minutes (7:30:02 PM to 7:42:03 PM on 2026-09-30), most of it waiting on LinkedIn and Claude.

Why cron and not a loop? A process that exits after every run can't leak memory or get stuck forever, and a crash only loses one run. The next one starts fresh 30 minutes later.

systemd: keeping the bot alive

The bot has to react within seconds at any hour, so it can't be a cron job. It runs as a **systemd service**. systemd is the Linux "init system": the first program that starts at boot, which then starts and supervises everything else. The service definition, `/etc/systemd/system/jobscout-bot.service`:

```
[Unit]
Description=Job Scout Discord Bot
After=network.target

[Service]
Type=simple
User=Haatim
WorkingDirectory=/home/Haatim/job-agent/job-scout
ExecStart=/home/Haatim/job-agent/job-scout/venv/bin/python /home/Haatim/job-agent/job-scout/bot.py
Restart=always
RestartSec=10

[Install]
WantedBy=multi-user.target
```

- `After=network.target`: don't start until networking is up (the bot needs the internet).
- `User=Haatim`: run with normal permissions, not as root.
- `Restart=always` + `RestartSec=10`: if the bot crashes or is killed, systemd restarts it 10 seconds later.
- `WantedBy=multi-user.target`: start it automatically at boot.

Useful commands: `sudo systemctl restart jobscout-bot` (restart after a code change), `systemctl is-active jobscout-bot` (is it running?), `sudo journalctl -u jobscout-bot` (its console output; **journald** is systemd's log store).

Logs

Each program writes its own log file with Python's `logging` module (timestamp, level such as INFO/WARNING/ERROR, message):

File	Written by	What's in it
`/var/log/jobscraper.log`	`scraper.py`	Every job considered and why it was kept or dropped (32 MB so far)
`/var/log/jobscout_bot.log`	`bot.py`	Reactions, commands, errors
`/var/log/jobscout_tailor.log`	`tailor.py` (also when run by `apply_prep.py`)	Every resume edit, rejection and reason
`job-scout/apply_prep.log`	`apply_prep.py`	Packet builds and failures

`tail -f /var/log/jobscraper.log` shows a run live. `grep "Alerted:" /var/log/jobscraper.log*` lists every alert in the current and rotated logs.

Log rotation. Without it, logs grow forever (the scraper log had reached 32 MB). `/etc/logrotate.d/jobscout` tells **logrotate**, Debian's standard tool run daily by a systemd timer, to rotate each log weekly or whenever it passes 20 MB, keeping 8 old copies gzipped (`jobscraper.log.1`, `.2.gz`, …). It uses `copytruncate` (copy the file, then empty it in place) because the programs keep their log files open, and moving the file would leave them writing to the moved copy.

Watchdog: knowing when something stops

A cron job that silently stops is the worst kind of failure: no errors, just no alerts. `heartbeat.py` handles it:

- At the end of every run, the scraper writes `.last_run` (finish time, number alerted, any error).
- The always-on bot checks it every 15 minutes. If no run has finished for **75 minutes** (two missed runs), it posts one ⚠️ warning in #job-alerts mentioning you, and one "✅ running again" when runs resume. Warnings fire once per outage, not every 15 minutes.
- Optional: set `HEALTHCHECK_URL` in `.env` to a healthchecks.io check (free for personal use). The scraper pings `/start` when a run begins and the base URL (or `/fail`) when it ends, and healthchecks.io emails you if pings stop. This covers what the bot can't: the whole server going down, which takes the bot with it. This technique is called a **dead man's switch**: silence, not an error message, triggers the alert.

Backups

`backup_db.py` copies `jobs.db` every night with SQLite's **online backup API**, which produces a consistent copy even if the scraper or bot is writing at that moment (copying the file with `cp` mid-write can capture a half-written, corrupt database). Copies are gzipped into `~/backups/` (about 2.5 MB each) and the newest 14 are kept. To restore: `gunzip -c ~/backups/jobs-DATE.db.gz > job-scout/jobs.db` with the bot stopped.

Configuration and secrets

Config files are plain text you can edit without touching Python:

File	Format	What it controls
`candidate_profile.yaml`	YAML	Who you are and what you want; pasted into Claude's scoring prompt
`scraper_config.json`	JSON	Search terms, locations, company boards, keyword lists, excluded companies
`experience_kb.yaml`	YAML	Your "knowledge base": contact info, education, every job and project; the source of truth for cover letters and form answers
`application_answers.yaml`	YAML	Standard form answers: work authorization, sponsorship, start date, graduation, voluntary self-identification, essay style
`ResumeTemplate.tex`	LaTeX	Your actual resume, in the typesetting language that produces the PDF
`CoverLetterTemplate.tex`	LaTeX	Cover letter layout with placeholders

YAML and **JSON** are both formats for structured data (lists and key/value pairs). JSON uses braces and quotes and is what APIs speak; YAML uses indentation and is easier for people to edit.

Secrets live in `.env`, a file of `NAME=value` lines loaded into **environment variables** by `python-dotenv` when a program starts. It is never committed to git. Current keys:

Variable	What it is
`ANTHROPIC_API_KEY`	Authorizes (and bills) Claude API calls
`DISCORD_BOT_TOKEN`	The bot's password to Discord
`DISCORD_WEBHOOK_URL`	Secret URL that posts into #job-alerts
`DISCORD_CHANNEL_ID`	#job-alerts
`REQUESTS_CHANNEL_ID`	#requests
`APPLICATIONS_CHANNEL_ID`	#applications
`DISCORD_USER_ID`	Your Discord account, for `<@you>` pings
`GOOGLE_SERVICE_ACCOUNT_JSON`	Path to the Google service-account key file (`~/.config/job-agent/google-sa.json`, permissions 600)
`JOB_TRACKER_SHEET_ID`	Which spreadsheet is the tracker

Permissions 600 is Unix shorthand for "only the owner can read or write this file." Anyone who read the key file could edit your Sheet, so nobody else should be able to.

Part 4: Collecting and filtering jobs (`scraper.py`, `career_sites.py`)

Source 1: LinkedIn through JobSpy

JobSpy (`python-jobspy`) is an open-source library that reads LinkedIn's public job search pages, the same ones a logged-out visitor sees, and returns the results as a **pandas DataFrame** (a table in memory). The scraper turns each row into a Python dictionary.

Every search term is paired with every location:

- **11 search terms:** Software Engineer Intern, Software Development Intern, AI Engineer Intern, Machine Learning Engineer Intern, Applied AI Intern, Applied ML Intern, AI Research Intern, Agentic AI Intern, Research Intern, Product Manager Intern, Technical Product Manager Intern.
- **4 locations:** San Jose, Santa Cruz, San Francisco, Remote.
- **44 searches per run**, each asking for up to 40 results posted in the last 24 hours with `job_type="internship"`. "Remote" is sent as location "United States" with the remote flag. There's a 2-second pause between searches (`time.sleep(2)`) to avoid hammering LinkedIn.

LinkedIn's terms of service prohibit scraping, so JobSpy's requests can be rate-limited or blocked by IP. That's a reason the career-site sources below were added. LinkedIn also hides a posting's real application link behind a sign-in, so LinkedIn alerts get packets only when the same role can be found on the company's own job board (see "Finding LinkedIn jobs on the company's own board" in Part 6).

Source 2: company job boards (`career_sites.py`)

Many companies don't host their own job pages; they use an **ATS** (applicant tracking system), a hosted product that lists jobs, collects applications and lets recruiters review them. Several ATSs publish every client's open jobs as a public **JSON API**: a URL that returns data instead of a web page. The scraper calls them directly:

ATS	Endpoint	Companies configured
Greenhouse	`boards-api.greenhouse.io/v1/boards/<board>/jobs?content=true`	20: Stripe, Databricks, Roblox, Figma, Anthropic, Cloudflare, Reddit, Discord, Airbnb, Coinbase, Robinhood, Dropbox, Pinterest, Lyft, Instacart, Datadog, Samsara, Scale AI, Asana, Affirm
Lever	`api.lever.co/v0/postings/<company>?mode=json`	2: Palantir, Spotify
Ashby	`api.ashbyhq.com/posting-api/job-board/<board>`	5: OpenAI, Notion, Ramp, Linear, Perplexity
Amazon	`amazon.jobs/en/search.json`	4 queries: SDE intern, ML intern, data science intern, PM intern
SmartRecruiters	`api.smartrecruiters.com/v1/companies/<id>/postings?q=intern`	none configured; learned boards are added automatically
Workday	`POST <tenant>.<wd>.myworkdayjobs.com/wday/cxs/<tenant>/<site>/jobs`	NVIDIA (`nvidia|wd5|NVIDIAExternalCareerSite`)
SimplifyJobs list	`raw.githubusercontent.com/SimplifyJobs/Summer2027-Internships/dev/.github/scripts/listings.json`	one file covering thousands of companies

The `<board>` part is a **slug**: a short, URL-safe name for the company on that ATS (`figma`, `scaleai`).

THE ADAPTER PATTERN

Each ATS returns a different JSON shape. Greenhouse calls the link `absolute_url`; Lever calls it `hostedUrl`; Ashby calls it `jobUrl`. Rather than teach the whole pipeline four formats, each source gets a small **adapter** function (`fetch_greenhouse`, `fetch_lever`, `fetch_ashby`, `fetch_amazon`) that translates its format into one shared shape, built by `_job()`:

```
{"title", "company", "location", "job_url", "description",
 "date_posted", "applicants": None, "site": "greenhouse", "board": "figma"}
```

This is the same shape a JobSpy row has, so everything downstream (`process_jobs`) handles all sources identically. Adding a new ATS means writing one adapter and nothing else. `board` was added on 2026-09-30 so the packet builder can find the application form later.

WORKDAY, SMARTRECRUITERS AND THE SIMPLIFYJOBS LIST (ADDED 2026-10-01)

- **Workday** (used by NVIDIA, Capital One and many large companies) has no documented public API, but its career sites are JavaScript apps that call a JSON API anyone can call: a `POST` to `/wday/cxs/<tenant>/<site>/jobs` with a search text ("intern") returns 20 postings per page with a title, location and a relative date like "Posted 3 Days Ago" (`_workday_posted` turns that into a timestamp). Descriptions need a second request per job, so they're fetched only for fresh postings with "intern" in the title. A board is written `tenant|wd-host|site`, read straight off the careers URL.
- **SmartRecruiters** has a documented, unauthenticated Posting API. The company id is the first path segment of a `jobs.smartrecruiters.com/<id>/...` link.
- **SimplifyJobs Summer 2027 Internships** is a community-maintained list (about 17,000 listings, around 4,400 open on 2026-10-01) that Simplify keeps fresh by scraping company career pages hourly. The bot downloads its `listings.json` once per run and keeps listings that are open, visible and not graduate-only (degrees listed as only Master's/PhD/MBA). It has no descriptions, so Claude scores these on title, company, locations and the listing's metadata (term, category, degrees, sponsorship), and the 📋 flag marks them in Discord. `_ats_from_url` recognizes when a listing's link is on Greenhouse, Lever, Ashby, SmartRecruiters or Workday; Greenhouse, Lever and Ashby ones get application packets like any career-site job. In the first trial, 159 of 3,738 open listings passed the title and age filters.
- **SAP SuccessFactors** (Sephora's jobs.sephora.com, and many large companies) publishes an RSS feed of its 20 newest postings with full descriptions at `/services/rss/job/`; `fetch_successfactors` reads it (configured as `"Company|https://jobs.example.com"`).

Watched companies. `watch_internships` in `scraper_config.json` (currently `["sephora"]`) lists companies where **every** internship is alerted, whatever the role: `is_watched_internship` keeps any posting from that company with a whole-word "intern"/"internship" in the title, past the role-keyword filter, and the scraper alerts it even if Claude's fit score is low (the score is still shown). These alerts carry a 👀 flag and, as watchlist companies, a gold color.

Learned boards. When a job is alerted from a company's board (found through Simplify, a career site, or the LinkedIn lookup), that board is saved in the `learned_boards` table, and every later run checks it directly alongside `scraper_config.json`. The config file itself is never edited by code, so a deploy or rollback can't clobber it. The first board learned was Pinterest's.

DETAILS THE ADAPTERS HANDLE


- **Double-escaped HTML (Greenhouse).** Greenhouse returns descriptions as `<p>Hello</p>`: HTML whose angle brackets were themselves encoded as **HTML entities**. `_html_to_text` parses once to decode the entities, sees tags are still present, and parses again to extract plain text.
- **Three date formats.** `_parse_dt` accepts ISO 8601 strings (`2026-09-24T17:24:36-04:00`), Lever's **epoch milliseconds** (milliseconds since 1970-01-01 UTC), and Amazon's `September 24, 2026`. Everything is converted to a **timezone-aware** UTC datetime so ages can be compared correctly.

- **Title matching** (`title_matches`). A posting survives only if its title:
  1. contains none of the excluded words (`senior`, `staff`, `principal`, `lead`, `director`, `phd`, `postdoc`, `sales`, `recruit`, `marketing` and others), and
  2. contains an intern keyword as a **whole word**, using the **regular expression** `\binterns?\b`. `\b` is a word boundary, so "Intern" and "Interns" match but "Internal", "International" and "Internals" don't, and
  3. contains a role keyword (`software`, `engineer`, `machine learning`, `data`, `research`, `product manager`, `agentic` and others).
- **Freshness.** Postings older than 72 hours (`max_age_hours`) are dropped.
- **In-run dedupe.** A `seen_urls` set skips a URL that appears twice in one run.
- **Fail soft.** If one company's feed errors (a 404, a timeout), it's logged and skipped; the other 30 sources still run.

Career sites are processed **before** LinkedIn each run, because companies often post there first and the company's own page is the canonical link.

The filter funnel (`process_jobs`)

Every candidate job goes through a sequence of checks, cheapest first. A job that fails any check is marked seen so it's never examined again.



The filter funnel

Lifetime counts from the scraper log: 1,870 jobs stopped by `quick_filter`, 9,160 by the experience filter, 67 by the 7-day duplicate check, 38,112 rejected by Claude, and 522 alerted. `seen_jobs` holds 49,731 URLs.

1. SEEN CHECK

`SELECT 1 FROM seen_jobs WHERE job_url = ?`. The `?` is a **query parameter**: the value is sent separately from the SQL text, so a URL containing quotes or SQL keywords can never be interpreted as SQL (**SQL injection**). Every query in the project is written this way.

2. `QUICK_FILTER`: FREE STRING CHECKS

- Company or title contains an `exclude_industries` term (currently none) or an `exclude_companies` term (`jobright`, a job aggregator that reposts other companies' listings).
- **Pay floor.** JobSpy reports pay as an amount plus an **interval** (hourly, yearly). The floor is $25/hour or $40,000/year, compared only against the matching interval. (A past bug compared everything to $40,000, so "$50/hour" looked too low.)

3. FULL PAGE FETCH (LINKEDIN ONLY)

Search results only contain a short snippet, so `fetch_full_job_details` downloads the actual posting page with `requests`, sending a browser-like **User-Agent** header (the string that identifies what software is making a request; some sites return different content to scripts). Then with BeautifulSoup it:

- Finds the description using a list of **CSS selectors** (patterns that identify page elements, like `.show-more-less-html__markup`), taking the first that contains over 200 characters.
- Finds the applicant count with regexes such as `(\d[\d,]+)\s+applicants?` and `Be among the first\s+(\d+)`.
- Detects reposts with `reposted\s+\d+\s+(minute|hour|day|week)s?\s+ago`, which LinkedIn embeds in reposted listings.

4. EXPERIENCE FILTER (A REGULAR EXPRESSION)

`EXPERIENCE_FILTER_RE` rejects any description that asks for 5 or more years of experience, before paying for a Claude call. It has three alternatives joined by `|` ("or"):

```
(?<![0-9-])([5-9]|\d{2})\+?\s*(?:to\s*\d+\s*)?years?\s*(?:of\s*)?(?:experience|exp\.?
|required|minimum|min\.?)\b
minimum\s+(?:of\s+)?([5-9]|\d{2})\s+years?
(?<![0-9-])([5-9]|\d{2})\s*\+\s*(?:years?|yrs?)\b
```

Reading the first one piece by piece:

- `(?<![0-9-])`: a **negative lookbehind**: the next character must not come right after a digit or hyphen, so "15" isn't read as "5" and "3-5 years" isn't read as "5 years."
- `([5-9]|\d{2})`: a single digit 5 to 9, or any two-digit number.
- `\+?`: an optional plus sign ("5+").
- `\s*`: any amount of whitespace.
- `(?:to\s*\d+\s*)?`: an optional range like "5 to 7". `(?: )` is a **non-capturing group**, grouping without saving the match.
- `years?`: "year" or "years" (`?` makes the `s` optional).
- `(?:of\s*)?(?:experience|exp\.?|required|minimum|min\.?)\b`: followed by "experience," "exp.," "required," etc.

It catches "5+ years of experience," "minimum of 7 years" and "10+ yrs," and ignores "1-3 years" and "a 5-year roadmap." The `re.IGNORECASE` flag makes it case-insensitive.

5. DUPLICATES AND REPOSTS

- **7-day same-role check.** `is_repost_by_title` compares the job with everything from the same company seen in the last 7 days, by **meaning, not exact wording**: `title_key` reduces a title to its core words (order-free, with years, "intern", filler and punctuation dropped), so "2027 Summer Intern – Machine Learning Engineer, AV/AI Platform" (LinkedIn) and "Machine Learning Engineer Intern - AV/AI Platform" (Simplify) count as one job. Seasons are kept apart: a Spring and a Summer program are two jobs, but a title with no season matches either. Company names ignore punctuation ("Rhoda AI" = "Rhoda-Ai"). Until 2026-10-04 this check required identical titles, and 10 of the 120 alerts since Oct 1 were duplicates (General Motors' 4 internships each came twice).
- **Repost signals.** `detect_repost` looks for words like "reposting" or "re-opening" in the title and first 600 characters of the description. A repost is still considered, but its "fresh" timestamp isn't trusted.

6. FRESHNESS OR FILTER (LINKEDIN ONLY)

`passes_or_filter` is how the system favors jobs you can apply to early. A LinkedIn job continues only if it's **under 2 hours old OR has fewer than 10 applicants**:

Age	Applicants	Repost?	Result
≤ 2 h	any	no	pass
any	< 10	any	pass
> 2 h	≥ 10 or unknown	any	fail
unknown	≥ 10 or unknown	no	pass (let Claude decide)
unknown	≥ 10 or unknown	yes	fail

Career-site jobs skip this step; they were already limited to 72 hours and have no applicant count.

Claude scoring (`claude_relevance_check`)

Only survivors of every free check reach Claude. The model is **Claude Haiku 4.5** (`claude-haiku-4-5-20251001`): Anthropic's small, fast, inexpensive model, well suited to a high-volume yes/no judgment.

THE PROMPT

The **prompt** is the text sent to the model. It's assembled from:

1. Your profile from `candidate_profile.yaml`: name, background, target roles, industries, locations, $25/hr minimum pay, experience level ("undergraduate … NOT enrolled in or pursuing a Master's or PhD"), and the **disqualifiers** (3+ years' experience, non-English language requirements, grad-student-only roles, with a note that "Bachelor's/Master's/PhD" listed as alternatives is fine).
2. **Rejection context**: your 15 most recent ❌ dismissal reasons from the `rejections` table (see "The feedback loop").
3. The job: title, company, location, and the first 3,500 characters of the description.
4. A **JSON schema** describing the reply (`SCORE_SCHEMA`):

```
{"relevant": true, "reason": "one sentence", "fit_score": 7,
 "experience_required": "0-1 years", "location_ok": true}
```

`max_tokens=1000` caps the length of the reply. A **token** is the unit models read and write, roughly three-quarters of a word; the cap keeps each call cheap and fast.

READING THE ANSWER

The schema is sent as a **structured output** (see "Anthropic (Claude)" in Part 8), so the reply always parses. Schemas can't express number ranges, so `fit_score` is clamped to 1-10 in code. A job is alerted only if `relevant` is true **and** `fit_score` is at least 5.

ERROR HANDLING: ERRORS ARE NOT REJECTIONS

This part exists because of a real incident. In September 2026 the Anthropic account ran out of credits; every call failed, the code treated each failure as "not relevant," and **702 jobs were permanently skipped**. Errors are now sorted into three kinds:

Kind	Examples (Anthropic SDK exception classes)	What happens
Account problem	`AuthenticationError`, `PermissionDeniedError`, "credit balance"	Job left **unseen** (retried next run). A module-level flag `_claude_unavailable` stops all further Claude calls this run. One ⚠️ Discord warning per day, tracked in the marker file `.last_api_alert`
Temporary outage	`RateLimitError` (HTTP 429), `APIConnectionError`, `InternalServerError` (HTTP 5xx)	Job left unseen, retried next run
Anything else	A refusal, or a reply cut off by `max_tokens` (`ClaudeJSONError`)	Treated as a rejection, so one bad job can't be retried forever

At the end of a run with an account problem, the packet step is skipped too, since it needs Claude.

The alert

Alerts are sent through a Discord **webhook**: a secret URL that accepts a message and posts it into one channel, no bot login needed. The message is an **embed** (Discord's card format) with:

- **Title** "Role @ Company," linked to the posting (the bot later reads this link and title back out of the embed).
- **Color:** gold for a watchlist company (Anthropic, OpenAI, NVIDIA, Databricks, Scale AI, Cohere, Mistral, Groq, Together AI, Perplexity, Cursor), spring green if under an hour old, otherwise blue.
- **Flags:** ♻️ REPOST, 🔥 FRESH, ⭐ WATCHLIST COMPANY, 🏢 FROM COMPANY CAREER SITE, 👀 applicant count.
- **Fields:** company, location, posted, applicants, source, and Claude's one-sentence "Why it fits."
- **Footer:** the reaction legend (👍 tailor, ✅ applied, ❌ dismiss).
- A `<@your-id>` **mention** in the message text so your phone gets a notification.

Then the job is marked seen. If it came from Greenhouse, Lever or Ashby it's added to `apply_queue` (Part 6). If it came from LinkedIn, the scraper first looks for the same role on the company's own board and queues that posting if it finds one.

Tailored files with every alert

Since 2026-10-26, tailoring runs only when you react 👍 on an alert, and #job-alerts holds nothing but alerts. Everything a reaction triggers is posted in the **actions channel** (`ACTIONS_CHANNEL_ID` in `.env`, defaulting to #applications, which can be renamed in Discord, e.g. to #reactions, without changing its ID): the "On it" note and the "📎 Tailored resume + cover letter: @ " files from 👍, the "✅ Logged application" note, and the "why are you passing?" question from ❌ (answer it there). Each reply links back to its alert. This applies to a reaction in any channel: ✅ on a 📎 message in #requests also answers in the actions channel. The scraper watchdog's warnings go there too. `bot.reply_channel_id` decides where replies go. (The #requests conversation itself, posting a link and the bot asking what you need, stays in #requests.) (From 2026-10-04 to 10-26 every alert was tailored automatically and the files posted under it in #job-alerts; that is `tailor_alerts`, still in `scraper.py`, behind `tailor_every_alert`, now `false` in `scraper_config.json`.)

Part 5: The Discord bot (`bot.py`)

How a Discord bot works

A Discord bot is a program that logs in with a **bot token** and holds a persistent **WebSocket** connection to Discord's **gateway**. A WebSocket is a two-way connection that stays open, so Discord can push **events** ("someone reacted," "a message was posted") to the bot the instant they happen, instead of the bot asking over and over.

The bot is built with **discord.py**, which is **asynchronous**: it runs an **event loop** that juggles many tasks in one thread. Functions defined with `async def` can pause at `await` (for example while waiting for Discord to respond) and let other events be handled in the meantime.

Intents declare which events the bot wants. This bot enables the defaults plus `message_content` (to read what you type in #requests; Discord calls this a **privileged intent** that has to be switched on in the developer portal) and `reactions`.

Events the bot handles

- `on_ready`: logged in; writes "Bot online" to the log.
- `on_raw_reaction_add`: a reaction was added anywhere. The "raw" version fires even for messages the bot hasn't cached (for example alerts posted before its last restart), which is why it's used instead of `on_reaction_add`. It ignores the bot's own reactions and any channel other than #job-alerts and #requests.
- `on_message`: any new message; used for commands (`!...`), dismissal reasons, and #requests conversations.

Emoji normalization. 👍🏽 is actually two Unicode characters: 👍 plus a **skin-tone modifier** (U+1F3FB to U+1F3FF). Some keyboards also add an invisible **variation selector** (U+FE0F). `normalize_emoji` strips both, so every variant counts as 👍.

Reactions

Reaction	What happens
👍	Replies "On it!", then runs `tailor.py <job_url> <channel_id>` as a **subprocess** (a separate program) with a 180-second timeout. `tailor.py` posts the resume and cover letter back itself, named `Haatim_Ali_<Company>_Resume.pdf` and `Haatim_Ali_<Company>_Cover_Letter.pdf`, and records which resume went with the job.
✅ (or the older 📨)	Reads the job URL and "Role @ Company" from the embed, writes a row to `applications`, looks up the resume used (`apply_prep.resume_used`), and writes the Google Sheet row. Replies with what changed in the sheet.
❌	Asks "Why are you passing?" and remembers that it's waiting for your answer. Your next message is saved to `rejections` as the reason ("skip" saves none).

Why tailoring runs in a subprocess, through `run_in_executor`. `subprocess.run` **blocks**: the calling thread waits until the program finishes. If the event loop itself waited 60 seconds, the bot would ignore every other event that minute. `loop.run_in_executor(None, ...)` hands the blocking call to a background **thread pool**, and the event loop keeps serving events while it runs. Running tailoring as a separate process also means a crash inside it can't take the bot down.

The #requests channel: a small state machine

A **state machine** is a program that behaves differently depending on which "state" it's in. #requests has two states per user:

1. **Waiting for a job.** You post a URL or a PDF. For a PDF the bot downloads it, extracts the text with `pypdf`, and saves it to a temporary file. It asks "What do you want?" with examples ("tailor everything, emphasize my Python automation experience", "just the cover letter, startup tone").

2. **Waiting for instructions.** Your reply becomes `--prompt` for `tailor.py` (“skip” means defaults), and the job goes back to state 1.

Pending state lives in two Python dictionaries in memory, `pending_requests` and `pending_rejections`, keyed by your Discord user ID. Being in memory means a bot restart forgets a half-finished conversation (a known limitation).

Commands

Command	What it does
`!applied <url> <Company> – <Role>`	Log an application made outside the bot
`!status <url> <status>`	Move an application to `phone_screen`, `interview`, `offer`, `rejected` or `withdrawn`; also updates the Sheet
`!note <url> <text>`	Attach a note
`!tracker`	Your pipeline, newest first, split into 1,900-character chunks (Discord’s limit is 2,000 per message)
`!stats`	Counts by status, total dismissals, top 5 dismissal reasons
`!help`	The command list

Part 6: Documents and applications

Resume tailoring (`tailor.py` + `resume_tailor.py`)

A SHORT LATEX PRIMER

LaTeX is a typesetting language: you write plain text with commands, and a compiler lays it out into a PDF with professional typography. `ResumeTemplate.tex` **is** your resume. Since 2026-10-25 it compiles line for line to `Haatim_Ali_Resume_v7.pdf` (the general software/AI-ML resume, also used on Overleaf). It loads the TeX Gyre Termes font (`tgtermes`) and falls back to Times if that isn't installed. If you update your own resume, update the template to match (and vice versa), and update `experience_kb.yaml`, which holds the same facts for cover letters and the fact-check.

- The **preamble** (everything before `\begin{document}`) loads packages (`times` for the Times font, `hyperref` for clickable links) and sets margins.
- **Macros** are reusable commands the template defines. For example, `\newcommand{\resitem}[1]{\item #1 \vspace{-6pt}}` defines `\resitem{...}` as "a bullet, then pull the next line up 6 points." That negative space is what makes your resume tight; bullets inserted as a plain `\item` look loose (a past bug).
- **Special characters** have meanings in LaTeX (`&` separates table columns, `%` starts a comment, `$` enters math mode, `_` means subscript), so literal ones must be **escaped**: `\&`, `\%`, `\$`, `\_`. Both `tailor.py` and `resume_tailor.py` contain escape functions for this.
- **Markers.** The tailorable bullets sit between comment lines like `% %%AIEA_BULLETS_START%%` and `% %%AIEA_BULLETS_END%%`. Because they start with `%`, LaTeX ignores them, but Python can find them with a regex and swap the bullets in between.
- **pdflatex** is the compiler. `compile_pdf` writes the `.tex` file into a **temporary directory**, runs `pdflatex -interaction=nonstopmode` (don't stop to ask questions on an error) with a 30-second timeout, and copies the PDF out.

THE PIPELINE, ONE CALL AT A TIME

`tailor.tailor(job_url, job_description)` runs these steps. Every Claude call here uses the **draft model**, `DRAFT_MODEL` in `claude_json.py`: **Claude Sonnet 5.5** (`claude-sonnet-5-5`) since 2026-10-01, previously Sonnet 4.6 (see "Choosing the draft model" in Part 8). Passes 2 and 3 get your knowledge base as a cached system block.

1. **Get the job description.** Passed in by `apply_prep.py`, or fetched: a plain HTTP request trying selectors such as `.job-description`, and if the page comes back nearly empty (sites behind a JavaScript bot check), a **headless browser** (Playwright running Chromium with no window) loads it and waits 5 seconds. Eightfold career sites (jobs.nvidia.com and other links with `?pid=`) are read through their public job API instead (`/api/apply/v2/jobs/<pid>`), which returns the real title, location and description. Whatever comes back must pass `looks_like_prose` (real sentences, not JSON or CSS); if nothing does, the bot replies that it couldn't read the posting instead of tailoring against junk.
2. **Pass 1: analyze the job** (Sonnet). Returns JSON: exact role title, company, a filename slug, 3 to 5 must-haves, 2 to 3 nice-to-haves, 12 to 15 ATS keywords, and the tone (formal, startup, technical, sales).
3. **Pass 2: match experience** (Sonnet). Compares `experience_kb.yaml` with the must-haves; returns which experience should lead, one story for the cover letter, and **gaps** (requirements you don't clearly meet) with a talking point for each.
4. **Pass 3: write the cover letter** (Sonnet). Three paragraphs, only real experience, no em dashes, a logistics line at the end.
5. **Resume edits** (Sonnet, `temperature=0.3`), then the fact-check (Sonnet, `temperature=0`), described next.
6. **Compile**, with the layout guard.
7. **Cover letter** is filled into `CoverLetterTemplate.tex` (`%%DATE%%`, `%%PARAGRAPH_1%%`…) and compiled. If it runs over one page, Claude is asked to shorten each paragraph and it's compiled once more.

Temperature controls randomness in a model's output: 0 gives the most predictable answer; higher values give more variety. Edits run at 0.3 (a little creativity in wording, mostly consistent); the fact-check runs at 0 (a judge should be consistent).

HOW RESUME EDITS ARE KEPT TRUTHFUL

Tailoring can change four things, all inside marker blocks in `ResumeTemplate.tex`; the header, the Leadership line, the camp-instructor bullets and the layout never change:

- **Bullets** in five sections: AIEA Lab (3 shown), Website Developer (3), JobAgent (4), Uplink (4), Pathwise (3). Since 2026-10-26 each section's bullets are picked from a **bullet bank**: the template's defaults plus approved alternates in `bullet_bank.yaml` (e.g. Uplink's 10 of 13 merged PRs, the Qwen vision model on an NVIDIA Brev GPU, the customer site and ops dashboard; JobAgent's 6-table SQLite database, nightly backups, the layout guard). Every alternate was checked against the real repos, PRs and logs, and a comment in the file says where each fact comes from. The same number of bullets is always shown per section.
- **Project order** (`%%PROJECTS%%`): JobAgent, Uplink and Pathwise in whatever order fits the job.
- **Coursework order** (`%%COURSEWORK%%`): all eight courses, most relevant first (a systems role leads with Computer Systems & Assembly and C).
- **Technical Skills** (`%%SKILLS%%`): 3 or 4 lines, regrouped and relabeled for the job ("Low-Level & Languages", "ML & GPU"…), using only skills in the template, `experience_kb.yaml` or the bank's `skill_extras` . `validate_skills` rejects any unknown or duplicate skill, labels over 26 characters, or dropping more than 4 skills; `fit_skills` first trims the last (least relevant) items off any line too long to print on one line.

1. **Extract.** `extract_sections` finds each marker block and pulls out the argument of every `\resitem{...}` , counting braces so nested ones like `\textbf{...}` don't end it early (a **brace-balanced parse**).
2. **Convert to editable text.** `latex_to_marked` turns `\textbf{Kubernetes}` into `**Kubernetes**` and unescapes symbols, so Claude sees clean text with Markdown-style bold. Each bullet gets an ID like `AIEA_BULLETS-0` .
3. **Ask for edits.** The prompt (`build_prompt`) gives the analysis, the job description, every bank bullet marked default or alternate, the projects, courses, current skills and the allowed skill list. Per section it allows: pick which bullets to show (exactly as many as the defaults) and their order, reword toward the job's terminology where it's true (about 40-55% of the bullets, 7 to 9 of the 17 shown, counting swapped-in alternates; required, not optional), and keep bold as it is (a bullet with no bold must stay without bold; where a bullet has bold, it may move onto a job-relevant term). The reply is JSON in the same shape, every ID exactly once. Because the bullets already fill their lines, the prompt says to make room by swapping words or dropping a minor detail (never a number) rather than adding words. If fewer than the target number of bullets come back changed, the bot asks once more (`build_retry_note` , temperature 0.5) and keeps whichever answer changed more; the log line `Resume edit pass: N bullet(s) changed` shows how many.
4. **Mechanical validation** (`validate_edit`), in code. An edit is rejected, and the original kept, if it:
   - is empty, or has unbalanced `**` markers
   - is more than 5% plus 6 characters longer (`MAX_GROWTH = 1.05` , `GROWTH_SLACK = 6`), or under 70% of the original length (`MIN_SHRINK = 0.70`)
   - drops any number from the original, or introduces a new one (found with the regex `\d+(?:\.\d+)?\+?%?` , which matches 5, 3+, 100%, 49.5)
   - removes all bold or adds more than one extra bold span (bold added to a bullet that had none is simply stripped, keeping the rewording)
   - adds an em dash (—) the original didn't have
5. **Pick and order check.** A section's picks are accepted only if they are exactly the right number of distinct bank IDs; the project and course orders only if they are a **permutation** of the originals (same items, just rearranged). Anything else keeps the defaults. An alternate used word for word needs no fact-check (it is pre-approved); a reworded alternate is checked against the alternate's own text.
6. **Independent fact-check** (`build_verify_prompt`). A second Sonnet call at temperature 0 sees only ORIGINAL and EDITED pairs and acts as a strict judge. It rejects relabeling ("Discord alerts" → "telemetry"), new tools or outcomes, and stronger claims ("led" for "helped", "production" for "demo"). Real catches: calling Pathwise's "reasoning pipeline" a "data pipeline," and adding "cross-functional" to a Montessori bullet. **If the check itself fails to run, every edit is discarded**: the safe failure is your original wording.
7. **Layout guard.** The untouched template is compiled once to count its text lines (a proxy for how full the page is). The tailored version must be one page and use no more lines. If it doesn't fit, `revert_one` puts back the original text of whichever edit grew the most (keeping the new order), recompiles, and repeats; when no rewordings are left, `revert_alternate` swaps the longest alternate back for an unused default, and last of all the skills go back to the template's lines (up to 25 attempts).

Every decision is logged to `/var/log/jobscout_tailor.log` , for example `{'id': 'MONTESSORI_BULLETS-0', 'status': 'rejected (fact-check)', 'reason': "Adds 'cross-functional' which is not stated or implied"}` .

Why so conservative? An earlier version let Claude rewrite bullets freely from the knowledge base. It produced a generic summary line, loose spacing, lost bold, deleted strong bullets, and slipped in claims you couldn't defend in an interview. A resume that reads as inflated does more harm than one that's merely untailored. The design principle: **the model proposes, code and a second model verify.**

SENDING THE RESULT


When run by the bot, `tailor.py` briefly logs in to Discord as a second, temporary client (`send_to_discord`), posts the PDFs with their `Haatim_Ali_<Company>_...` names plus the gaps as an attached `..._Interview_Prep.txt` file (since 2026-10-04; they used to be posted as chat text), and exits. It records the message's **jump URL** (a permanent link to that Discord message) in `tailored_resumes`, so a later ✅ can link the exact resume in your Sheet.

Application packets (`apply_prep.py`)

> **Status since 2026-10-04: form filling is switched off.** Haatim fills applications with each site's own autofill. Every alert instead gets its tailored resume and cover letter (see "Tailored files with every alert" in Part 4). The packet, form-fill, watcher and remote-filler code described below is kept in the repo but disabled (`"application_packets": false` in `scraper_config.json`), and the remote-browser services were removed from the VPS.

THE QUEUE

`apply_queue` is a table where each row is one job and its **status** moves through a fixed set of states:



apply_queue status lifecycle

`enqueue` skips a job if the same **posting** is already queued (any status) or logged as applied, comparing `posting_key` rather than raw links: the Lever/Ashby posting UUID or the Greenhouse job number. The same job often arrives under different links (Simplify's `.../application?embed=true` vs Ashby's plain link, a company site's `?gh_jid=` vs `job-boards.greenhouse.io/.../jobs/<n>`), which once queued Rhoda AI twice. At the end of each scraper run, the scraper starts `apply_prep.py --pending 3` **as a separate process** with a 20-minute timeout. It takes the 3 queued jobs with the highest fit score. Separate process, for two reasons: tailoring is slow, and `tailor.py` configures logging when it's imported, which would otherwise hijack the scraper's log file.

LinkedIn alerts are queued too when the same role is found on the company's own board (next section). Only jobs alerted **after** this feature was deployed (2026-09-30) are queued; the tens of thousands already in `seen_jobs` are never re-examined. `apply_prep.py --url <posting>` builds a packet for any Greenhouse, Lever or Ashby posting on demand.

FINDING LINKEDIN JOBS ON THE COMPANY'S OWN BOARD (`FIND_ON_ATS`)

LinkedIn listings are usually copies of a posting that lives on the company's ATS. LinkedIn only reveals the real "apply" link to signed-in users, and signing the server into your LinkedIn account would risk getting it banned. So instead, for every LinkedIn alert the scraper searches the company's **public** job boards for the same role:

1. **Guess the board name** (`slug_candidates`). The company name is lowercased, legal words (Inc, LLC, Corp, Technologies) are removed, and common suffixes are tried: "Clay" → `clay`, `claylabs`, `clayhq`, `clayinc`, `clayai`, `clayapp`, `claycareers`, `clayjobs`; "Scale AI" → `scaleai`, `scale-ai`, `scale` and their suffixed forms. Each is tried on Greenhouse, Lever and Ashby. A board that doesn't exist returns HTTP 404 and is skipped.
2. **Match the title** (`same_job`). Both titles are **normalized**: lowercased, text in parentheses or brackets removed ("(London, United Kingdom)"), and seasons and years dropped, so "Software Engineer Intern - Summer 2027" and "Software Engineer Intern (Summer 2027)" both become "software engineer intern." They must be at least 85% similar by `difflib.SequenceMatcher`, which measures how much of two strings lines up.
3. **Match the description.** A different company can own the same board name and have an identically titled internship, so the descriptions must also overlap. The overlap is the **Jaccard similarity** of their word sets: shared words divided by all distinct words, using words of 4+ letters. It must be at least 0.25. If either description is too short to compare (under 30 words), only an exact normalized title counts.
4. **Break ties** (`pick_match`). Companies often post the same title several times (Figma has Software Engineer Intern for Summer 2027 in SF, Winter 2027 in SF, and Summer 2027 in London). Candidates are narrowed by location words shared with the LinkedIn listing, then by how many words of the full title (seasons included) they share, then by description overlap. **If it's still a toss-up, nothing is queued**: a wrong match would mean applying to the wrong job.

Checked against live boards on 2026-09-30: Clay's LinkedIn alert found `jobs.ashbyhq.com/claylabs/...`; "Software Engineer Intern - Summer 2027" in San Francisco found Figma's SF summer posting and not the London or winter ones; a Barclays program with no public board found nothing. The lookup takes about 1 to 4 seconds per LinkedIn alert and only runs for alerted jobs.

READING THE REAL FORM

Instead of guessing what an application asks, `resolve_form` reads the form's actual questions from the ATS:

ATS	How the questions are read	How the form URL is built
Greenhouse	`GET boards-api.greenhouse.io/v1/boards/<board>/jobs/<id>?questions=true` returns every question with its field name, type, required flag and options, plus the `compliance` block (voluntary self-identification)	`job-boards.greenhouse.io/<board>/jobs/<id>`
Lever	Downloads the `/apply` page and parses each `li.application-question` with BeautifulSoup: label text, input name, type, radio/checkbox/select options. A ✱ in the label means required	`jobs.lever.co/<company>/<id>/apply`
Ashby	POSTs a **GraphQL** query named `ApiJobPosting` to `jobs.ashbyhq.com/api/non-user-graphql`; returns `applicationForm.sections[].fieldEntries[]`	`jobs.ashbyhq.com/<org>/<id>/application`

GraphQL is an API style where the client sends a query describing exactly which fields it wants, and gets back JSON in that shape.

Many Greenhouse companies host listings on their own site (`stripe.com/jobs/search?gh_jid=8128745`). The job ID is in the `gh_jid` **query parameter**, and the board slug comes from the scraper, which is why `career_sites.py` now records `board`. Greenhouse's country and city fields aren't in the API, so they're added by hand.

Every ATS's questions are normalized to one shape (the adapter pattern again):

```
{"key": "question_19438734004", "label": "Why do you want to join Figma?",
 "type": "textarea", "required": true, "options": []}
```

Types: `text`, `textarea`, `select`, `multiselect`, `file`, `location`. Ashby yes/no (`Boolean`) questions become a `select` with options Yes and No.

DRAFTING THE ANSWERS

One call to the draft model (`build_answer_prompt`, `max_tokens=16000`) receives `application_answers.yaml`, the job description and the question list, with `experience_kb.yaml` in the cached system block. The reply's schema (`answer_schema`) has **one property per question key**, and each dropdown's property is an `enum` of that question's real options (plus `""` for "no answer"), so Claude physically can't answer a question that doesn't exist or pick an option that isn't on the form. "No answer" is `""` rather than `null` because the API rejects schemas with many nullable fields (it hit that limit on Waymo's 21 questions). Option lists longer than 60 (such as every university in the world) are replaced by a note telling Claude to give the text to search for. The rules:

- Dropdown answers must be one of the listed options, copied exactly.
- Voluntary self-identification uses your saved answers in `application_answers.yaml` (kept out of git; see `application_answers.yaml.example`). Anything not covered gets the decline option.
- Essays follow `essay_style` (60 to 150 words, one concrete project tied to something specific in the job) and **may not claim personal experiences or opinions that aren't in the knowledge base**. This rule was added after the first test packet said "Figma is one of the few products I actually use."
- No em dashes, en dashes or `--`.
- A fact the knowledge base doesn't contain (GPA, age) gets `null` and is listed as unknown. **No guessing.**
- **Disclosures and attestations** (conflicts of interest, relationships with company employees, ties to government officials, background checks, criminal history, non-competes) are answered **only** from `application_answers.yaml`. If the saved answers don't cover the question, it's left blank and listed for you. These are legal statements you're signing, so they're never inferred from the knowledge base or the job description. Added 2026-10-01 after Robinhood's form asked several.

WHICH CONTACT DETAILS GO WHERE

Where	Name	Email	Location
Resume and cover letter header (`ResumeTemplate.tex`, `CoverLetterTemplate.tex`)	Haatim Ali	personal Gmail	Fremont, CA
Application form fields (`application_answers.yaml`)	Haatim / Ali; **Haatim Tahir Ali** where a form asks for the name on a government ID	**UCSC school email**	Fremont, CA (city fields pick "Fremont, California, United States")

Because forms use the school email and documents use the Gmail address, recruiters may reply to either, so check both. The values live in `application_answers.yaml` on the VPS, which is kept out of git; `application_answers.yaml.example` shows the shape.

VALIDATING THE ANSWERS IN CODE

The model's output is checked like the resume edits:

- `strip_dashes` replaces any `–`, `—` or `--` in answers of 40+ characters with a comma. It skips short answers so option labels are never altered.
- `validate_answers` throws out any `select` answer that isn't a real option, filters `multiselect` answers down to real options, ignores keys that aren't questions, and flags every required question left without an answer as **needs you**.

THE PACKET

`output/packets/<company>-<role>/` contains `packet.json` (form URL, ATS, files, and every question with its answer and `needs_you` flag), the tailored resume and the cover letter. "📦 Packet ready" is posted in #applications with the count of drafted answers and any questions that need you.

SUBMITTING (ON YOUR MAC)

Every ATS used here puts a **CAPTCHA** on its application form. A CAPTCHA is a test designed to tell people and programs apart. Greenhouse uses Google **reCAPTCHA Enterprise**, which is usually invisible: it scores how human the session looks and only shows a puzzle if suspicious. Lever uses **hCaptcha**. They exist to block automated submissions, so submitting from the server would mean evading bot detection. Instead, a person does the last click.

Saying "submit my queue" in Claude Code runs the `/submit-applications` skill:

1. `apply_prep.py --list` over SSH shows the ready packets; `scp` copies them to `~/job-agent/applications/packets/`.
2. Any needs-you questions are asked in one batch. Reusable answers can be saved to `application_answers.yaml`.
3. **Claude in Chrome** (a browser extension that lets Claude click, type and upload in your real Chrome) opens each form in a new tab and fills it. Greenhouse's dropdowns are **comboboxes** (a text box with a filtered list): click, type the option, pick it. Files are attached with the extension's upload tool.
4. You review, do the CAPTCHA if one appears, click Submit and say "done." **The skill never clicks Submit.**
5. `apply_prep.py --submitted <url>` on the VPS (`mark_submitted`):
   - sets the queue status to `submitted` and writes a row in `applications`
   - posts "✅ Applied: *role* at *company*" in #applications with the resume PDF attached, pinging you
   - records that message's link in `tailored_resumes`
   - writes the Google Sheet row with Resume Used linking to it

THE WATCHER: FILLING WITHOUT BEING ASKED

Saying "submit my queue" is optional. Run `/loop 30m /submit-applications watch` in a Claude Code session on your Mac and leave it open. Every 30 minutes it:

1. logs any tab you've submitted ("Thank you for applying" page): ✅ in #applications, Sheet updated, tab closed
2. asks the VPS for ready packets (`apply_prep.py --ready-json`) and copies new ones
3. if the Chrome window isn't visible, posts one "📦 ready, bring Chrome forward" ping and stops (Chrome ignores typing in hidden windows)
4. otherwise fills every new packet in its own tab with the fill plan
5. posts one ping in #applications (`apply_prep.py --notify ... --ping`): "🖱️ Ready to submit in Chrome: …" plus any "❓ needs you" items (open questions or agreements, which it never answers on its own)

State lives in `~/job-agent/applications/watch_state.json` so nothing is filled or announced twice. It never clicks Submit. Requirements: the Mac awake, Chrome open on the current desktop, and that Claude Code session running; each tick uses some of your Claude usage even when there's nothing to do.

FILLING FAST: THE FILL PLAN (`FORM_FILL.PY`)

Clicking through a form one field at a time takes dozens of round trips between Claude and the browser. `form_fill.py` (runs on the Mac) turns a packet into one ready-made batch for the extension's `browser_batch` tool:

1. **Navigate** to the form. Greenhouse always uses the embed form (`/embed/job_app?for=<board>&token=<id>`), because some companies, like Waymo, redirect to their own site and bury the form in an iframe.
2. **Setup:** one JavaScript call installs small helper functions on the page (`window.__f`: find a field, fill text, open a dropdown, pick an option, check everything), so each later step is a one-line call.

3. **Dropdowns:** three small steps each: `__f.open(field)`, real typing, `await __f.pick("exact option")`. Greenhouse dropdowns are **react-select** components that only respond to genuine keystrokes, so typing can't be faked with JavaScript. `pick` waits for the option to appear with a **MutationObserver** (a browser API that reports changes to the page) instead of polling on a timer, and clicks the option whose text matches exactly. That avoids fuzzy mistakes like "Male" matching "Female."
4. **Text fields last**, all in one call: React only notices a value set through the input's native setter followed by an `input` event, and Greenhouse wipes name and email if they're set before the form finishes loading.
5. **Check:** `__f.verify` reads every field back and lists anything that doesn't match.

Agreements (privacy policies, interview rules) are held out of the batch until you approve them. Figma's race question only appears after "Are you Hispanic/Latino?" is answered, so the plan answers that first. Tested 2026-09-30 on Figma's form: 13 dropdowns and 8 text fields in one batch, about 50 seconds, every field correct.

Keep the Chrome window visible while filling. Chrome throttles timers in hidden windows (minimized, behind others, or on another desktop) and drops real keystrokes there, which is why early fills were slow and some typing silently went nowhere. The helper warns when the tab is hidden. Closing other tabs doesn't matter, because Claude only works in its own tab group.

Fill everything, then submit. The skill now asks all its questions in one round, fills every queued form in its own tab, then hands you one list. Each tab whose title turns to "Thank you for applying" is logged and closed.

POSTING TO #APPLICATIONS (`POST_DISCORD`)

Unlike alerts, which use a webhook, these messages are posted as the bot through Discord's **REST API**: `POST https://discord.com/api/v10/channels/<id>/messages` with the header `Authorization: Bot <token>`. A **REST API** is the request-response style of web API: one HTTP request, one response. Posting as the bot works in any channel the bot can see, and the response contains the new message's ID.

Attaching a file uses a **multipart/form-data** request: the body is split into parts, one holding the message JSON (`payload_json`) and one holding the PDF bytes (`files[0]`). The permanent message link is built as `https://discord.com/channels/<server id>/<channel id>/<message id>`. Discord IDs are **snowflakes**: 64-bit numbers that encode their creation time, unique across all of Discord.

If `APPLICATIONS_CHANNEL_ID` isn't set, notices fall back to the #job-alerts webhook.

Part 7: Data

SQLite primer

SQLite is a complete SQL database stored in a single file (`jobs.db`, 10 MB), with no database server to install or keep running. Programs open the file directly with Python's built-in `sqlite3` module. It fits here because every program that uses the database runs on the same machine.

- A **table** is like a spreadsheet tab with fixed columns.
- A **PRIMARY KEY** is the column that uniquely identifies a row; here it's almost always `job_url`, so the same job can't be stored twice.
- `INSERT OR IGNORE` adds a row unless one with that key already exists; `INSERT OR REPLACE` overwrites it.
- `CREATE TABLE IF NOT EXISTS` makes table creation safe to run every time a program starts, which is how new tables appear without a separate setup step (a lightweight **migration**).
- **Concurrency and WAL.** The scraper, bot and packet builder can all touch `jobs.db`. By default SQLite locks the whole file while writing, so a reader waits. The database now uses **WAL (write-ahead logging)** mode: writes go to a side file (`jobs.db-wal`) that is merged in later, so readers never wait for a writer and a writer only waits for another writer. The scraper sets it with `PRAGMA journal_mode=WAL`, and the setting is stored in the database file itself. Python still waits up to 5 seconds for a write lock before raising "database is locked."

The tables

Table	Rows now	Written by	Columns	Purpose
`seen_jobs`	49,731	scraper	`job_url` (key), title, company, date_found	Never process a job twice; 7-day duplicate check
`applications`	4	bot, `apply_prep.py`	`job_url` (key), title, company, status, date_added, notes	Your application pipeline
`rejections`	0	bot	id (auto-increment), job_url, title, company, reason, date_rejected	Feeds the scoring prompt
`apply_queue`	1	scraper, `apply_prep.py`	`job_url` (key), title, company, ats, board, fit_score, status, packet_dir, note, date_added, date_updated	Application packets
`tailored_resumes`	0	`tailor.py`, `apply_prep.py`	`job_url` (key), filename, message_url, date_added	Which resume went with which job

Dates are stored as ISO 8601 text in UTC (`2026-09-30T19:42:03+00:00`), which sorts correctly as plain text.

The feedback loop (how it "learns")

When you dismiss a job with ❌ and give a reason, it goes into `rejections`. On every scoring call, your 15 most recent reasons are pasted into Claude's prompt under "You've recently passed on these roles and here's why (use this to calibrate)." Claude then scores similar jobs lower.

No model is retrained. The system adapts by changing **what goes into the prompt**, a technique called **in-context learning**. It's free, it takes effect on the next run, and you can read exactly why a decision changed. There's also an optional second source (`MEMORY_REPO_PATH`, a git repository with `rejection-patterns.md` that the bot appends to and pushes); it isn't configured on this server. With 0 dismissals so far, the loop hasn't had anything to learn from yet.

Why data lives in two places

- **SQLite on the VPS** is the working memory of the programs: fast, local, no setup.
- **The Google Sheet** is the view you actually read and edit by hand. `sheets_sync.py` keeps it in step with the database.

Part 8: Outside services

Google Sheets (`sheets_sync.py`)

ACCESS

The code signs in with a Google **service account**: a robot identity with its own email address and a private key file, instead of your Google password. You shared the Sheet with that email as an Editor, the same way you'd share it with a person. `gspread` handles the **OAuth 2.0** exchange (trading the key for a short-lived access token) behind the scenes.

Settings are read **when a sync runs, not when the module is imported**. That fixed a real bug: `bot.py` imported `sheets_sync` before calling `load_dotenv()`, so the settings looked unset forever and syncing silently never happened.

SHEET LAYOUT (SINCE 2026-10-29)

Tab	What it shows
Dashboard	Totals (applications, companies, in progress, response rate, rejected, offers), a status breakdown with coloured bars, applications per week (table + chart), companies with several roles, and recent activity. Every number is a formula over Applications, so it is always current.
Applications	One row per position, newest first: A Company, B Role, C Status (dropdown, coloured chip), D Applied, E Updated, F Source, G Location, H Posting (`Open ↗` link), I Resume (`Tailored ↗` link or "Default"), J Notes, K Roles @ Co.
Targets	Your hand-made list of companies, with formulas for how many roles you have applied to there and the latest status ("Not yet" in grey).
Consulting, Deferred MBA programs, Oracle, Miscellaneous	Your own lists; the code never touches them.
Product (old)	The previous layout, hidden, kept as a backup.

Statuses: To Apply, Applied, Assessment, Interviewing, Offer, Rejected, Closed (expired or an assessment never taken), Withdrawn.

Several roles at one company are separate rows that share the Company. Column K is one array formula in K1 that counts them, and the Dashboard lists every company with more than one role.

New rows are **appended and then sorted** by Applied date (newest first), not inserted at row 2: inserting at row 2 would shift every formula's `A2:A` reference to `A3:A`.

`python sheets_sync.py --layout` re-applies all formatting (header, banding, chips, dropdown, filter, widths) and rebuilds the Dashboard. It never changes data rows.

WHERE A ROW GOES (`FIND_ROW`)

Only the Applications tab is searched, in order:

1. The same posting, compared by host + path (`url_key`), so share links and tracking query strings don't create duplicates → update Status and Updated.
2. Same company and same role (both normalized) → update Status and Updated.
3. Otherwise → a new row with today's date (Pacific) in Applied and Updated.

Logging an application that is already tracked only bumps Updated. An "Unknown Company" is named from the posting link when the host matches a company already in the sheet (`guess_company` : careers.cisco.com → Cisco). Markdown leftovers like `**url**` are stripped. Companies are compared after `normalize_company` (lowercase, no

Inc/LLC/Corp/Technologies/Systems/Labs).

RESUME

Column I gets `=HYPERLINK("https://discord.com/channels/…", "Tailored ↗")`, a link to the Discord message holding that exact PDF, or “Default” if the job was never tailored. Formulas only work when written with `value_input_option="USER_ENTERED"`. Status-only updates leave column I alone.

REJECTIONS FROM EMAIL

`email_scan.py` (below) reads htali@ucsc.edu and writes rejections, assessments, interviews, offers and missing applications into Applications through `record_email`. Before it existed, rejections were read from haatimta@gmail.com by Claude Code on request.

FAIL SOFT

`record_safe` wraps every sync. A Google outage or a permissions problem is logged as a warning and returns nothing; the bot keeps working.

Gmail inbox check (`email_scan.py`)

Since 2026-09-30 every application uses **htali@ucsc.edu**, so that inbox is where companies answer. `email_scan.py` reads it twice a day and keeps the tracker current.

Access. The **Gmail API** with the **`gmail.readonly` scope**: the code can list and read messages, nothing else (it can’t send, delete, label or move mail). Sign-in uses **OAuth 2.0 for installed apps**: an OAuth client (“Desktop app”) in the same Google Cloud project as the Sheets service account, and a one-time browser sign-in as htali@ucsc.edu on the Mac (`python email_scan.py --auth <client.json>`). That saves a **refresh token** (a long-lived key that gets fresh short-lived access tokens) in `gmail_token.json`, which is git-ignored and copied to the VPS. A service account can’t be used here: reading a person’s Gmail with one needs a Workspace admin (domain-wide delegation).

One run:

1. List messages matching a broad query: mail from applicant-tracking systems (Workday, Greenhouse, Ashby, Lever, SmartRecruiters, iCIMS, Jobvite, CodeSignal, HackerRank, Wellfound and more), subjects with “application”, “interview”, “assessment” and the like, or the word “unfortunately”. The first run reads back to 2026-08-01; later runs read the last 4 days.
2. Skip any message already in the `email_events` table, so each email is handled once.
3. Claude Haiku (temperature 0, structured output) labels each one: rejection, assessment, interview, offer, confirmation or other, plus company, role and a 12-word summary. Anything that isn’t clearly about an application is “other” and ignored.
4. `sheets_sync.record_email` finds the row: same company (tolerating suffixes such as “Inc.” and longer names), then the closest role by text similarity when the company has several. A company with one tracked row always matches (email titles often differ from the posting’s). A named role that matches none of the company’s rows is a new application. A confirmation that can’t be pinned to one of several roles changes nothing and asks nothing; any other email that can’t be pinned down is left for Haatim and the summary asks him. A row only moves forward (`STATUS_RANK`): a late “we received your application” never undoes a rejection, and only an offer beats a rejection. An email about an untracked application adds a row with Source “Email”.
5. One summary in #reactions listing what changed. It pings Haatim for assessments, interviews, offers and questions.

If the sign-in expires or is revoked, the run posts a warning in #reactions with the command to sign in again. `!inbox` in Discord runs a check immediately.

Cron: 15:05 and 01:05 UTC (about 8 am and 6 pm Pacific), log `/var/log/jobscout_email.log`.

Discord

- **Server channels:** #job-alerts (alerts only; you react there), #applications (the actions channel: everything a reaction triggers, plus ✅ notices), #requests (tailor any URL or PDF), #general.
- **Three ways the code talks to Discord:**
  1. **Webhook** (scraper alerts): simplest, one channel, no login.
  2. **Gateway WebSocket** (`bot.py` , and `tailor.py` briefly): receives events in real time.
  3. **REST API with the bot token** (`apply_prep.py`): one-off posts with attachments, returns message IDs.
- **Mentions** are written `<@user id>` in message text, which triggers a notification.
- **Limits:** 2,000 characters per message (the code splits at 1,900 to be safe).
- **Permissions:** the bot can read and post in its channels but doesn't have "Manage Channels," which is why you created #applications by hand.

Anthropic (Claude)

Every Claude call is an HTTPS request to Anthropic's **Messages API** through the official Python SDK, authenticated with `ANTHROPIC_API_KEY` and billed per token (see Anthropic's pricing page for current rates).

Where	Model	Calls	Settings
Scoring each job	Claude Haiku 4.5 (`SCORE_MODEL`)	1 per job that survives the free filters	`max_tokens=1000`
Tailoring: analyze job	Claude Sonnet 5.5 (`DRAFT_MODEL`)	1	`max_tokens=16000`
Tailoring: match experience	Sonnet 5.5	1	cached knowledge base
Tailoring: cover letter	Sonnet 5.5	1 (+1 if over a page)	cached knowledge base
Tailoring: resume edits	Sonnet 5.5	1	`temperature=0.3` on models that accept it
Tailoring: fact-check	Sonnet 5.5	1 if anything changed	`temperature=0` on models that accept it
Packet: form answers	Sonnet 5.5	1	cached knowledge base

So a scored job costs one Haiku call, and a full packet costs about six draft-model calls. Every call goes through one helper, `claude_json.ask_json` .

Structured outputs. Each call sends a JSON schema in `output_config.format` . The API then **constrains generation to the schema**: the model can only produce tokens that keep the reply valid, so it always parses and always has every required field. That replaced the old approach (ask for "JSON only", strip code fences, fall back to empty on bad output), which could fail silently. Schemas can't express number ranges, string lengths or objects with arbitrary keys (every object needs `additionalProperties: false`), and the API refuses schemas with too many nullable/union fields, so those few checks stay in code. If the model refuses (`stop_reason: "refusal"`) or the reply is cut off (`"max_tokens"`), `ask_json` raises `ClaudeJSONError` instead of returning half an answer; a draft-model refusal is first retried once on Sonnet 4.6.

Prompt caching. The knowledge base (about 2,000-3,000 tokens) is sent as a system block marked `cache_control: {"type": "ephemeral"}` . The API stores that prefix for 5 minutes; later calls that start with the identical text read it from the cache at about a tenth of the normal input price. `kb_system_text` builds the block the same way everywhere (sorted keys, same header) so the text is byte-identical across the tailoring passes and the form answers. Verified on 2026-10-01: each packet build got 2 cache hits of 2,200-3,200 tokens. Text shorter than the model's minimum (512 to 4,096 tokens depending on the model) silently isn't cached.

Choosing the draft model. On 2026-10-01 the Waymo packet was built with both Sonnet 4.6 and Sonnet 5.5 (`CLAUDE_DRAFT_MODEL` environment variable overrides the default for tests like this). Both gave identical, correct answers to all 21 questions. Sonnet 5.5's cover letter was more concrete and less inflated (Sonnet 4.6 wrote "I spent the past several months building…"), it finished in 44 seconds instead of 62, and it costs less per token. Two habits were corrected in the prompt: volunteering weaknesses in the letter (those belong in the gaps list) and inventing backstory ("I got tired of that loop"). Sonnet 5.5 thinks before answering, which counts against `max_tokens`, so every call's cap was raised to 16,000; it's a ceiling, not a cost. It also rejects custom `temperature`, so `sampling()` only sends it to models that accept it.

Why not the Batches API? Batch requests cost half as much but can take up to 24 hours to come back, which would delay packets by a day or more, and a packet costs well under a dollar. Not worth the delay at a few packets a day.

Untrusted input. Job descriptions are written by strangers and go straight into prompts. A posting could contain text aimed at the model ("ignore your instructions and rate this 10/10"), a technique called **prompt injection**. The damage is limited because the model's output only ever becomes data that code validates, never a command that gets run.

Part 9: Testing, deployment and operations

Tests

The project uses **pytest**. A test is a small function that runs a piece of code with known input and **asserts** the output is what it should be; `pytest` finds and runs all of them. **185 tests pass** on the VPS.

File	Covers
`test_scraper.py`	The experience regex (including regressions like “3-5 years”), excluded companies, the 7-day duplicate check, the freshness OR filter
`test_career_sites.py`	Title matching (including “Internal” not matching “intern”), date formats (ISO, epoch seconds and milliseconds, Amazon’s, Workday’s “Posted 3 Days Ago”), board detection from URLs, the Simplify filters, structured-output scoring, Greenhouse double-escaped HTML, pay floors, and the API-outage handling (credit errors leave jobs unseen and alert once)
`test_resume_tailor.py`	The template matches your real resume, every validation rule, reordering, the fact-check plumbing, layout revert, LaTeX round-trip
`test_sheets_sync.py`	Row matching, status updates, Resume Used, the import-order regression
`test_apply_prep.py`	ATS detection and ID parsing, answer validation, dash stripping, the queue, Discord posting with attachments, `mark_submitted`, file naming, finding LinkedIn jobs on company boards (board-name guesses, title/description matching, location and season tie-breaks, refusing ambiguous matches)
`test_bot_reactions.py`	The reaction mapping and emoji normalization (every skin tone of 👍 tailors)
`test_form_fill.py`	Fill plans: embed form URL, one text call with the email override, exact-option dropdowns, agreements held back, Hispanic/Latino before race
`test_claude_json.py`	The shared Claude helper: schema payload, refusal and cut-off handling, the Sonnet 4.6 retry, temperature only where accepted, stable cached knowledge-base text
`test_reliability.py`	The scraper heartbeat (warn once, confirm recovery, healthchecks pings) and database backups (consistent, gzipped, pruned)

Techniques used:

- **Fakes.** `FakeWorksheet` imitates a Google Sheet in memory, so Sheet logic is tested without touching Google.
- **Monkeypatching.** pytest’s `monkeypatch` temporarily replaces something during one test, for example swapping `requests.post` for a function that records the call instead of hitting Discord.
- **`tmp_path`**: a fresh temporary folder per test, so database tests use a throwaway `jobs.db`.
- **Regression tests**: a test written for a bug that already happened, so it can never silently come back.

Run them with `venv/bin/python -m pytest -q --ignore=test_discord.py --ignore=test_linkedin.py`. Those two files are manual scripts that hit real services, not unit tests.

Where the code lives and how it’s deployed

- **Source of truth:** the `vps` branch of the private GitHub repo `Haatim-Ali/job-agent-private`. Changes are written and tested on your Mac (`~/job-agent`), pushed there, and pulled by the VPS, whose `~/job-agent` is a git checkout of that branch (since 2026-10-01). The VPS reads the private repo with a **deploy key**: an SSH key that GitHub grants read-only access to that one repository, so a compromised server can’t change your code or see your other repos. Your Mac’s `vps` branch is backed up to the **private** GitHub repository `github.com/Haatim-Ali/job-agent-private` (git remote `private`; push with `git push private vps`). The public repository `Haatim-Ali/job-agent` is a fork of a collaborator’s project (`jsho0/job-agent`); GitHub doesn’t allow forks to be private, so this work isn’t pushed there, and its `master` branch is the original shared project, which the VPS copy has diverged from.

- **Deploying a change:** commit on the Mac, then `bash deploy.sh`. It refuses to run with uncommitted changes, pushes to the private repo, then on the VPS: pulls (fast-forward only), runs the full test suite with the VPS's own packages, and **if any test fails, resets back to the previous commit** and stops. If they pass, it restarts the bot. The scraper needs nothing: cron starts a fresh process with the new code on the next run.
- **Continuous integration (CI):** `.github/workflows/job-scout-tests.yml` runs the same tests on GitHub's servers for every push to `vps` that touches `job-scout/`. A red ❌ on the commit in GitHub means something broke. Free private-repo minutes cover this easily (one run is about 5 minutes, mostly installing packages).
- **Dependencies:** `job-scout/requirements.txt` pins the exact versions running on the VPS, so the environment can be rebuilt identically and CI tests what production runs.
- **Rolling back** by hand: `git reset --hard <previous commit>` on the VPS, or revert the commit on the Mac and deploy again.
- **Before 2026-10-01** code was copied with `scp` into dated backup folders. Those were deleted on 2026-10-01 once everything was in git; the two files that existed only there are in `archive/vps-old-2026-10-01/`.
- **Secrets stay out of git.** `.env*` files (except `.env.example`) and `application_answers.yaml` are ignored. A snapshot commit on 2026-09-28 had included `.env.save` with the live Discord bot token; it was untracked on 2026-10-01 (it only ever reached the private repo).

Troubleshooting runbook

Symptom	Where to look	Likely cause
⚠️ "scraper hasn't finished a run" in Discord	`crontab -l`, `tail /var/log/jobscraper.log`, `ls /tmp/jobscraper.lock`	cron line removed, a run hanging while holding the lock, or the venv broke after an update
No alerts for hours	`tail /var/log/jobscraper.log`; look for "Claude unavailable"	API credits ran out (you'll also get a ⚠️ in Discord), or simply no new matches
`deploy.sh` says tests failed	its output; it has already rolled back	fix on the Mac, commit, deploy again
Database corrupted or deleted	`~/backups/`	restore last night's copy (see "Backups")
Reactions do nothing	`systemctl is-active jobscout-bot`; `journalctl -u jobscout-bot`	Bot crashed and is restarting, or the token changed
👍 says "Something went wrong"	`/var/log/jobscout_tailor.log`	LaTeX compile error or Claude error
Sheet not updating	`/var/log/jobscout_bot.log`, lines starting "Sheets sync"	Sheet no longer shared with the service account, or the key file moved
No 📦 packets	`apply_prep.py --list`; `job-scout/apply_prep.log`	No new career-site alerts yet, or a prep failure (the reason is in the queue's note column)
A packet answer is wrong	`packet.json`	Fix `application_answers.yaml` or `experience_kb.yaml` so future packets get it right

Part 10: Design decisions and limitations

Design decisions worth explaining

- **Two programs, not one.** Scraping is batch work (run, finish, exit): what cron is for. Reacting to clicks has to happen instantly at any hour: an always-on process. Separating them means a scraper crash can't take the bot down, and vice versa.
- **Cost-ordered funnel.** String checks and regexes are free and instant; a Claude call costs money and about a second. Putting the free filters first means Claude sees roughly 4 in 5 candidate jobs instead of all of them, and the expensive Sonnet pipeline only runs on jobs that already passed Haiku.
- **The right model for each task.** Haiku for high-volume yes/no scoring; Sonnet where writing quality matters.
- **Adapters for sources and forms.** Each job board and each application form format gets a small translator into one shared shape. Adding a source touches one function.
- **The model proposes, code verifies.** Resume edits, form answers and fit scores are all checked in code (and by a second model for resume facts). Nothing the model writes reaches an employer unchecked.
- **Safe failure.** When a check can't run, the system falls back to the conservative choice: original resume wording, the job left unseen for retry, a question flagged for you instead of guessed.
- **Errors are not rejections.** An outage should cause a retry, not silently lost jobs (the 702-job lesson).
- **Humans do the last click.** Packets are prepared around the clock; submitting stays with you, since the forms are CAPTCHA-protected and an application can't be taken back.
- **Config over code.** Search terms, companies, your profile and your standard answers live in YAML/JSON.
- **Everything is marked seen.** Rejected jobs are recorded too, which keeps runs fast and avoids paying for Claude twice on the same posting.
- **Fail soft.** One broken feed, a failed page fetch or a Sheets error is logged and skipped; the run continues.

Known limitations

- **In-memory conversation state.** A bot restart forgets a pending ❌ reason or #requests conversation.
- **LinkedIn scraping** can be blocked. LinkedIn alerts get packets only when the company's own Greenhouse, Lever or Ashby board can be found by name; companies on other systems (Workday, iCIMS, their own sites) or with unusual board names stay plain alerts.
- **Amazon postings** are alerted but get no packets (Amazon isn't a supported form type).
- **Company-slug file collisions.** Tailored PDFs are compiled as `Resume_<company>.pdf` in `output/`, so two roles at the same company overwrite each other there. Packets and Discord hold their own copies, so nothing is lost, but `output/` only has the latest.
- **Packets only for new alerts.** Jobs seen before 2026-09-30 aren't queued unless you run `--url`.
- **`tailored_resumes` starts empty.** Resume Used links only exist for jobs tailored after 2026-09-30.

Glossary

Adapter. A small function that converts one data format into a shared one, so the rest of the code only deals with one shape.

API (application programming interface). A defined way for programs to talk to each other. A web API is a URL that returns data (usually JSON) instead of a web page.

Async / await / event loop. A style of concurrency where one thread runs many tasks by switching between them whenever one is waiting (`await`). The event loop is the scheduler doing the switching.

ATS (applicant tracking system). Software companies use to post jobs and collect applications: Greenhouse, Lever, Ashby, Workday. Also used loosely for the keyword-scanning these systems do on resumes.

Blocking call. A function call that makes its thread wait until it finishes.

Brace-balanced parsing. Reading nested `{ }` by counting opens and closes, so an inner `}` doesn't end the outer group.

CAPTCHA. A test meant to tell people and programs apart. reCAPTCHA (Google) and hCaptcha are the two used here.

Combobox. A form field that's a text box plus a filtered dropdown list.

cron / crontab. The Linux scheduler, and its configuration table of "when" plus "what to run."

CSS selector. A pattern that identifies elements on a web page, like `.job-description` (anything with that class).

Dedupe. Removing duplicates.

Embed. Discord's rich message card: title, link, color, fields, footer.

Environment variable. A named value handed to a program by its environment, commonly used for secrets. `.env` files store them.

Epoch time. A timestamp counted as seconds (or milliseconds) since 1970-01-01 00:00 UTC.

Escaping. Writing a special character so it's taken literally, like `\&` in LaTeX.

Fake / mock / monkeypatch. Test stand-ins: a fake is a simple working imitation, a mock records how it was called, and monkeypatching temporarily swaps a real function for one of these.

Gateway (Discord). Discord's WebSocket endpoint that pushes real-time events to bots.

GraphQL. An API style where the request describes exactly which fields to return.

Headless browser. A real browser engine running with no window, controlled by code (Playwright here).

HTML entity. An encoded character in HTML, like `<` for `<`.

HTTP status codes. Three-digit results of a web request: 200 OK, 403 forbidden, 404 not found, 429 too many requests, 5xx server error.

In-context learning. Changing a model's behavior by changing what's in its prompt, without retraining it.

Intents (Discord). The event categories a bot subscribes to. Privileged intents such as message content need to be enabled explicitly.

ISO 8601. The standard date format `2026-09-30T19:42:03+00:00`.

JSON / YAML. Text formats for structured data. JSON is what APIs use; YAML is indentation-based and friendlier to edit.

Jump URL. A permanent link to a specific Discord message.

LaTeX / pdflatex. A typesetting language and the compiler that turns it into a PDF.

Lookbehind (regex). A condition on what comes *before* the current position, without consuming it. `(?<!...)` means "not preceded by."

Macro (LaTeX). A user-defined command, like `\resitem`.

Migration. A change to a database's structure. Here done with `CREATE TABLE IF NOT EXISTS` at startup.

Multipart/form-data. An HTTP request body split into parts, used to send files together with other fields.

OAuth 2.0. The standard protocol for granting a program limited access to an account through short-lived tokens.

Permutation. The same items in a different order.

Primary key. The column that uniquely identifies each row in a table.

Prompt / prompt injection. The text given to a model; and an attack where text inside the input tries to override the instructions.

Query parameter. In a URL, the `?key=value` part (`gh_jid=8128745`). In SQL, a `?` placeholder whose value is passed separately, which prevents SQL injection.

Regex (regular expression). A pattern language for matching text. `\b` word boundary, `\d` digit, `\s` whitespace, `?` optional, `+` one or more, `*` zero or more, `|` or, `( )` group.

REST API. Request/response web API: one HTTP request, one response.

scp / SSH. Secure file copy and secure remote shell, both over an encrypted connection authenticated with a key pair.

Service account. A non-human Google account used by programs, with its own key file.

Slug. A short, URL-safe name, like `figma` or `scaleai`.

Snowflake. Discord's 64-bit unique ID format, which encodes when the object was created.

SQL / SQLite. The standard database query language, and a database engine that stores everything in one file.

SQL injection. An attack where input text is interpreted as SQL. Prevented with query parameters.

State machine. A program whose behavior depends on which of a fixed set of states it's in, with defined transitions between them.

Subprocess. A separate program started by another program.

systemd / journald. The Linux system manager that starts and supervises services, and its log store.

Temperature. A model setting for randomness: 0 is most predictable, higher is more varied.

Thread pool / executor. A set of background threads that run blocking work so the main loop stays free.

Timezone-aware datetime. A timestamp that knows its offset from UTC, so comparisons across timezones are correct.

Token (model). The unit models read and write, roughly three-quarters of an English word. **Token (Discord bot).** The bot's secret login credential.

User-Agent. The header identifying what software is making a web request.

Virtual environment (venv). A private, per-project folder of Python packages.

VPS (virtual private server). A rented virtual machine in a data center, running 24/7.

Webhook. A secret URL that lets a program post into one Discord channel without logging in as a bot.

WebSocket. A long-lived, two-way network connection, used for real-time events.

Changelog

2026-10-29: inbox check for htali@ucsc.edu. New `email_scan.py`: read-only Gmail API access, Claude Haiku labels each recruiting email, `sheets_sync.record_email` updates the matching Applications row (never backwards; asks when several roles could match), summary in #reactions, `!inbox` command, cron twice a day. 15 tests added. `PRIVACY.md` added for the Google sign-in screen (production mode needs a privacy policy link).

2026-10-29: tracker sheet redesigned. New Dashboard, Applications (one row per position, status chips, dates, source, links) and Targets tabs; the old Product tab is hidden as "Product (old)", other tabs untouched. `sheets_sync.py` now writes only to Applications, matches postings by host + path, names "Unknown Company" rows from the link, records Applied/Updated dates, and sorts newest first. Data moved over: 82 applications; one duplicate NVIDIA row dropped and two KLA rows for the same req merged. From Gmail: 4 AMD applications, Architexor and GAO Tek (Wellfound, expired), ByteDance AI Platform (assessment invite 10/5) and TikTok (CodeSignal invite expired 10/10). New statuses `assessment` and `closed` in `!status`. Tests rewritten for the new layout.

2026-10-26: every reaction answers in #reactions. A ✅ on a tailored-files message in #requests had its "Logged application" reply posted in #requests; replies to reactions in any channel now go to the actions channel (renamed #reactions in Discord).

2026-10-26: school email. Resume, cover letter and knowledge base now use htali@ucsc.edu instead of haatimta@gmail.com.

2026-10-26: #job-alerts is alerts-only. Alerts are no longer tailored automatically (`tailor_every_alert: false`); 👍 tailors on demand. Every reply to a reaction on an alert (tailored files, applied, dismiss question) and the watchdog warning now go to the actions channel (#applications by default, `ACTIONS_CHANNEL_ID` to override), with a link back to the alert. 3 tests added.

2026-10-26: real per-job tailoring. Word swaps inside fixed bullets left resumes for different roles nearly identical (a Systems Software Engineering resume changed two words). The tailor now picks each section's bullets from a bank of verified alternates (`bullet_bank.yaml`), rewords them, and reorders projects and coursework, and regroups Technical Skills from Haatim's real skills (`validate_skills` , `fit_skills`). New template markers: `%%COURSEWORK%%` , `%%PROJECTS%%` , `%%SKILLS%%` . The layout guard also reverts alternates and skills. Tested live on two NVIDIA roles: the Systems resume leads with Computer Systems & Assembly, C and Linux/systemd work; the Deep Learning one with C++, Linear Algebra, deep learning training and an "ML & GPU" skills line. 11 tests added.

2026-10-26: resumes came back untailored. Two NVIDIA Workday roles (Autonomous Vehicles, Deep Learning) produced resumes differing only in one word and the project order. The job descriptions were read correctly; Claude was returning all 17 bullets unchanged, because the prompt said the resume "must look identical", called the tailoring "light", and (since v7) said to keep the outcome at the start, while the 5% length cap left no room on page-filling bullets. Fix: the prompt now requires rewording 7 to 9 bullets, allows rewording both the outcome and the "by …" part, and says to make room by swapping words or dropping a minor detail (never a number); if too few bullets come back changed, the bot retries once. Tested live on both postings: 7 and 8 bullets reworded (was 0 and 1). 3 tests added.

2026-10-25: v7 base resume. Every bullet rewritten result-first (outcome, then "by …" how), after comparing with a friend's resume that did better in recruiting. Camp cut to 2 bullets; a Leadership line (Alpha Kappa Psi Historian) added under Education. The tailor prompt now tells Claude to keep the outcome at the start of each bullet.

2026-10-25: v6 base resume. v5 plus more of the resume reviewer's feedback: centered header, no bold in bullets, Campus Involvements and Interests removed, camp adoption clause cut; a fourth bullet each for JobAgent (JS-heavy career sites read via job APIs and Playwright) and Uplink (photo accuracy, ElevenLabs retries) to fill the page. Fixed a v5 bug: `\DisableLigatures` with no option also disabled `--` , `---` and quote ligatures, so pdfLaTeX printed them literally; it's now `\DisableLigatures[f]` . The tailor prompt no longer hardcodes a bullet count.

2026-10-25: v5 base resume. Haatim preferred the older two-line layout (name left, contact right; role and city on line one, company and dates on line two; bold numbers). `ResumeTemplate.tex` is now v5: that layout with v4's accurate content, Uplink added, JobAgent rewritten to match the current bot, "Technical Skills" grouped as Languages / Frameworks & Libraries / Cloud, Data & DevOps / AI/ML, and ligatures disabled under pdfLaTeX (`microtype` `\DisableLigatures`) so ATS parsers read "file" rather than a joined glyph. Projects now run JobAgent, Uplink, Pathwise. KB bullets synced.

2026-10-25: v4 layout update. Education is now one line like the jobs (“Bachelor of Science in Computer Science, University of California, Santa Cruz” with “Expected March 2028” on the right, since many postings filter on graduation month). Job entries show the city again next to the dates. Uplink’s ElevenLabs claim now matches merged work (retries under the rate limit; the browser-transcript fallback is in an unmerged PR). Test count says 200+.

2026-10-25: NVIDIA links tailored against the wrong text. jobs.nvidia.com is a JavaScript app, so the plain fetch got its theme JSON (over 200 characters, so accepted as the “job description”). Two different NVIDIA roles (a world-models research intern and a technical marketing intern) produced byte-identical resumes. Fix: Eightfold job API for `?pid=` links, a `looks_like_prose` check on every fetch path, scripts/styles stripped before reading the page body. Also, Claude kept adding bold to v4’s unbolded bullets, so whole rewordings were rejected as “too much bold” and resumes came out barely tailored; the bold is now stripped and the rewording kept. 5 tests added.

2026-10-25: CI green again. GitHub Actions had failed on every push since early October: `test_draft_answers_sends_schema_and_cached_kb` read the personal `application_answers.yaml`, which isn’t in git, so it only passed on the Mac and VPS. The test now uses `application_answers.yaml.example`.

2026-10-23: v4 base resume. `ResumeTemplate.tex` now matches Haatim’s v4 resume, revised after a resume reviewer’s feedback: centered header without a city, “Class of 2028” and the degree spelled out, Campus Involvements removed, “Role, Company” on one line with no cities, the AIEA Lab’s full name (AI Explainability and Accountability), camp dates as months, no bold in any bullet, standalone past-tense bullets, Uplink rewritten around Haatim’s own part (A2A runtime, photo-accuracy work, evaluation) with the teammate’s repo link replaced by Haatim’s fork (github.com/Haatim-Ali/uplink), and “Additional” replaced by a bullet-free Technical Skills section (Languages, Frameworks & Tools, Concepts). `resume_tailor.py` now rejects any bold added to an unbolded bullet and tells Claude not to add bold. `experience_kb.yaml` bullets, titles and dates synced (interests and involvements kept there as cover-letter facts). 2 tests added.

2026-10-22: new base resume. `ResumeTemplate.tex` and `experience_kb.yaml` now match Haatim’s v3 resume: Fremont header, updated coursework, Uplink added as a fifth tailorable section (`UPLINK_BULLETS`), reworded bullets, regrouped skills (Languages, Frameworks & Tools, AI/ML & Agents). Tests updated for the new wording. The KB’s skills are now grouped the same way instead of technical/core.

2026-10-11: repo made public, server address removed. The repo is now `Haatim-Ali/job-agent-v2` (renamed from `job-agent-private`) and public. The VPS address, hostname and login no longer appear in the code or docs: `deploy.sh`, the README and this guide use the SSH alias `jobagent-vps`, defined only in `~/.ssh/config` on the Mac (`deploy.sh` also accepts `VPS=user@host`).

2026-10-01 (evening): status check and doc audit. The VPS runs commit `4060f85`, matching the private repo. In the day’s 23 scraper runs it alerted **38 jobs**, with a few one-off connection timeouts to Greenhouse/Lever boards that were skipped and retried on the next run (expected “fail soft” behavior). Application queue: **5 submitted** (Figma, Waymo, Muon Space, Pinterest, Robinhood), 3 ready (Trajectory, Quadric AI Kernel Engineer, Rhoda AI), others being prepared or skipped. Doc updates: disclosure-question rule, which contact details go on documents vs forms, and the resume template’s one deliberate difference from `Haatim_Ali_Resume.pdf` (Fremont).

2026-10-06: Sephora internship watch. New SuccessFactors source (RSS) for jobs.sephora.com and `watch_internships`: every Sephora internship is alerted with a 👀 flag regardless of role or score. Sephora had no internships posted at setup.

2026-10-04: duplicate alerts fixed. The same-role check now matches reworded titles (core words, seasons kept apart) instead of identical text. Replayed against the 120 alerts since Oct 1, it would have caught 10 true duplicates and no different jobs.

2026-10-04: tailored files with every alert; form filling switched off. Every alert now gets its tailored resume and cover letter posted under it (`tailor_alerts` in `scraper.py`). Application packets, the Mac fill skill, the watcher and the remote filler are disabled: Haatim uses each site’s own autofill. Remote-browser services (Xvfb, x11vnc, noVNC, filler) removed from the VPS; Tailscale stopped. Before the switch, 6 applications were submitted with the fill flow (Figma, Waymo, Muon Space, Pinterest, Robinhood, Trajectory, Quadric AI Kernel).

2026-10-01: location is Fremont, CA. Resume and cover letter headers, `experience_kb.yaml`, `application_answers.yaml` and the form filler's city field changed from San Jose to Fremont. Job search locations are unchanged. Robinhood (Data Science Intern) was submitted with San Jose just before the change.

2026-10-01: Ashby packets fixed. The Ashby form query asked for a field Ashby doesn't have (`descriptionPlainText`); Ashby rejected the query and the code read the error as "no questions," so 5 packets were built with an empty question list. The description now comes from the public job-board feed, and a query error or an empty form now fails the packet instead of passing silently. The 5 packets were rebuilt.

2026-10-01: duplicate packets fixed. The queue now compares posting IDs, not links (Rhoda AI had been queued twice via Simplify's and Ashby's different link forms).

2026-10-01: "university" removed from the internship keywords. It let Pinterest's full-time "University Grad Software Engineer 2027" through the title filter and into the packet queue (skipped). Regression test added.

2026-10-01: more sources, Claude upgrades, watcher. SimplifyJobs Summer 2027 list, Workday (NVIDIA) and SmartRecruiters adapters, and `learned_boards` (boards of alerted jobs are checked directly from then on). `claude_json.py`: structured outputs on every Claude call (form answers pinned to real question keys and options), the knowledge base as a shared cached system block (2 cache hits per packet), drafting moved to Sonnet 5.5 after a side-by-side test, refusal fallback to Sonnet 4.6. Watch mode for `/submit-applications` plus `apply_prep.py --notify` / `--ready-json`. Batches API considered and skipped (up to 24-hour latency for small savings).

2026-10-01: reliability. Scraper watchdog (`heartbeat.py`: bot warns in Discord after 75 minutes without a finished run; optional healthchecks.io), `flock` so runs can't overlap, nightly consistent database backups (`backup_db.py`, 14 kept), SQLite WAL mode, log rotation (`/etc/logrotate.d/jobscout`; the 32 MB scraper log was rotated), pinned `requirements.txt`, the VPS converted to a git checkout of the private repo (read-only deploy key) with `deploy.sh` (tests on the VPS, automatic rollback), GitHub Actions CI, rewritten `CLAUDE.md` and README, and `.env.save` (live bot token) removed from tracking. 162 tests passing.

2026-09-30: faster form filling. New `form_fill.py` and `test_form_fill.py` (10 tests): a packet becomes one browser batch (helpers installed once, exact-option dropdown picks, text fields last, read-back check). The submit skill fills every form before handing off. Found while testing: hidden Chrome windows throttle and drop input, Greenhouse resets name/email during load, and Figma's race question depends on the Hispanic/Latino answer. Also: the packet builder now reads Greenhouse's separate demographic survey, and `application_answers.yaml` holds the application email, the legal name for government-ID fields, the permanent address, citizenship, the export-license answer and "always yes" for relocation. It's kept out of git because it's personal; `application_answers.yaml.example` shows the format.

2026-09-30: LinkedIn alerts can get packets. New `find_on_ats` in `apply_prep.py`: for each LinkedIn alert, the scraper looks for the same role on the company's own Greenhouse, Lever or Ashby board (guessed board names, then title, description, location and full-title checks) and queues that posting. Prompted by a Clay alert (score 9) that got no packet because it came from LinkedIn; Clay's board is `claylabs` on Ashby. First live test also caught a wrong match (Figma London instead of SF), fixed by preferring the matching location and full title and refusing ambiguous matches. 147 tests passing. Backup: `~/job-scout-backup-2026-09-30-ats-lookup/`.

2026-09-30: this document rewritten as a complete technical guide: server and process model (SSH, venv, cron, systemd, logs), every filter with its exact rule and lifetime counts, the scoring prompt and error taxonomy, the Discord bot's event model, the LaTeX and truthfulness pipeline, packets, data, outside services, testing, deployment, a troubleshooting runbook, known limitations and a glossary.

2026-09-30: application packets, #applications and Resume Used

- Added `apply_prep.py`, `application_answers.yaml`, the `apply_queue` table and the `/submit-applications` Claude Code skill (on the Mac, in `~/.claude/skills/`). Career-site alerts are queued automatically; each scraper run builds up to 3 packets. `career_sites.py` now records each posting's ATS board so the form can be found.
- Checked live forms first: Greenhouse (reCAPTCHA Enterprise) and Lever (hCaptcha) both protect their application forms, so auto-submitting from the server was dropped in favor of fill-in-Chrome, human-submits.

- The first test packet (Figma, Software Engineer Intern Summer 2027) had an invented claim in an essay (“I use Figma”) and “--“ used as a dash. The prompt now forbids claims not in the knowledge base, and dashes are stripped from essays in code.
- Voluntary self-identification answers added to `application_answers.yaml`.
- New Discord channel **#applications** (`APPLICATIONS_CHANNEL_ID` in `.env`): 📦 packet ready and ✅ applied notices, posted as the bot. Job alerts stay in #job-alerts.
- Tailored files are now named `Haatim_Ali_<Company>_Resume.pdf` / `Haatim_Ali_<Company>_Cover_Letter.pdf`.
- The Google Sheet’s Resume Used column is now filled (a link to the exact resume, or “General/default resume”); new `tailored_resumes` table.
- Fixed “Jujitsu” → “Jiu-jitsu” in `ResumeTemplate.tex` and `experience_kb.yaml` to match the real resume.
- Backups on the VPS: `~/job-scout-backup-2026-09-30-apply/` and `~/job-scout-backup-2026-09-30-resume-used/`. 139 tests passing.

2026-09-29: new reactions. 👍 now tailors the resume and ✅ marks a job applied (previously ✅ tailored and 📨 marked applied). 📨 still works as “applied” so reactions on older alerts behave as expected. Skin-tone variants of 👍 are accepted. 5 new tests (102 total).

2026-09-28: career sites, pay fix and sheet sync, built on the live VPS code (local branch `vps`; deploy pending)

- Found that the VPS copy had already been retargeted to Haatim’s internship search (SWE, AI/ML, research, PM; San Jose, Santa Cruz, SF, Remote; Jobright excluded; web UI removed). A first draft built from the GitHub fork was set aside so none of that would be overwritten; all new work starts from a snapshot of the server code.
- **Bug fix:** the pay filter compared every salary to $40,000/year, so an internship listed at $50/hour was rejected as “too low.” It now uses the pay interval JobSpy reports ($40k yearly, $25 hourly).
- Added `career_sites.py`: 20 Greenhouse, 2 Lever and 5 Ashby boards plus Amazon, checked before LinkedIn, postings under 72 hours old.
- The same title at the same company within 7 days is now skipped, so a role on both LinkedIn and a career site alerts once.
- Added `sheets_sync.py`; 📨 and `!status` update the Google Sheet once credentials are configured.
- Deployed to the VPS the same day (backup at `~/job-scout-backup-2026-09-28/`). Google service-account key stored at `~/.config/job-agent/google-sa.json` (permissions 600) and the two settings added to `.env`.
- **Bug found in the first real test:** a 📨 reaction logged the application but didn’t update the sheet, with no error. `bot.py` imports `sheets_sync` *before* it calls `load_dotenv()`, and `sheets_sync` read its settings at import time, so it always saw them as unset. Fixed by reading the settings when a sync runs, logging when a sync is skipped, and adding a regression test. The Neuralink application from that test was written to row 84. Lesson: settings read at import time depend on import order.
- **Found through the first live run: the Anthropic API credits had run out** (current outage since 9/26, 1:33 AM server time; an earlier one began 7/26). Every Claude call failed, and the scraper treated each failure as a rejection and marked the job seen, so **702 jobs were permanently skipped** and no alerts went out.
- Fixed: account errors (no credits, bad key) and temporary outages (rate limits, connection errors, server errors) now leave the job **unseen so the next run retries it**. After an account error the run stops calling Claude, and the bot posts one ⚠️ Discord warning per day. A one-off failure for a single job (e.g. Claude returns unreadable output) is still treated as a rejection, so no job can be retried forever.
- Lesson: failure paths need the same care as success paths. “Error” and “rejected” looked the same to the code, so an outage silently turned into lost data.
- 74 tests passing.
- **2026-09-29: resume tailoring rebuilt.** Tailored resumes had a generic headline, loose bullet spacing (bullets inserted as `\\item` instead of the template’s tighter `\\resitem`), no bold, deleted bullets, and wording drawn from the knowledge base instead of the real resume. Replaced with the baseline-preserving pipeline described in “How resume tailoring works”, added `resume_tailor.py` and 19 tests (93 total), and synced the template’s Campus Involvements line to the current resume. Old files backed up on the VPS at `~/job-scout-backup-2026-09-29-tailor/`.
- **2026-09-29:** credits added. The 5:00 PM run was the first fully working run on the new code: 87 jobs scored, 84 rejected, **3 alerted** (Rhoda AI, SwingVision, Meta), 0 skipped for API errors.